



QUOTE

510 Corporate Dr, Ste A
 Escondido CA 92029
 760-796-7999

Page 1 of 2
Date
Estimate #
Terms
FOB

11/22/2021
 QT11317
 50%, Bal prior to shipping
 Factory

Bill To



Ship To



Item	QTY	Description	Unit Price	Amount	Tax Rate
T-HOR-LT-JBBT-007	2	7 BBL / 850 L Horizontal Jacketed Brite Lower Tank for Stacked Assembly - 14.7 PSI (1 Bar) Includes: 1.5" butterfly valves 2" pressure vacuum relief valve 1.5" Perlick sample valve Pressure gauge 1.5" end cap Sintered SS carb stone assembly - Zahm Nagel Level gauge assembly 3/8" SS ball valve for CO2 inlet Shadowless manway CIP - spray ball Multiple glycol zones Fully welded cladding Adjustable tank leveling pads	7,900.00	15,800.00	6.0%
T-HOR-UT-JBBT-007	2	7 BBL / 850 L Horizontal Jacketed Brite Upper Tank - 14.7 PSI (1 Bar) Includes: 1.5" butterfly valves 2" pressure vacuum relief valve 1.5" Perlick sample valve Pressure gauge 1.5" end cap Sintered SS carb stone assembly - Zahm Nagel Level gauge assembly 3/8" SS ball valve for CO2 inlet Shadowless manway CIP - spray ball Multiple glycol zones Fully welded cladding Adjustable tank leveling pads	7,300.00	14,600.00	6.0%
T-BBT-007-Parts-Pkg	4	7 BBL Brite Beer Tank - Parts Package	0.00	0.00	0.0%
CCP 4/8 24VAC	1	Cellar control Panel (Up to 8 Controllers) Includes: Nema 4X enclosure prewired with all controls and relays. 24VAC glycol solenoid controller transformer. main power disconnect.	1,695.00	1,695.00	6.0%
RTD 9.5	4	RTD, 9.5" Probe	135.00	540.00	6.0%
P11958	4	3/4" Brass Ball Valve, 24V AC/DC, Manual Override with 30' Cord	118.00	472.00	6.0%
<p>Quotes are valid for 15 days.</p> <p>PRICE DOES NOT INCLUDE SHIPPING CHARGES Due to the current state of volatility with third party freight, we are unable to estimate freight at this time</p> <p>Please note, not all tanks are suitable for 1/2 batches without modifications.</p> <p>The parts package included with cellar tanks DO NOT INCLUDE the Temp Controller, RTD's, or Solenoid Valves. If needed, please request the item(s) to be added to your order.</p> <p>PAYMENT TERMS: Deposit required to initiate order: \$17,546.71</p>					



QUOTE

Page 2 of 2
Date
Estimate #

11/22/2021
 QT11317

510 Corporate Dr, Ste A
 Escondido CA 92029
 760-796-7999

Item	QTY	Description	Unit Price	Amount	Tax Rate
		<p>Balance due upon completion of the Equipment and prior to shipment.</p> <p>Any delay in receipt of the above funds will result in a delay in shipping of the Equipment</p> <p>Price subject to change without notice.</p> <p>Estimated manufacturing 8-10 weeks and shipping 5-10 weeks (pending shipping delays).</p>			

CREDIT CARD INFO:
 Credit Card charges of \$5,000 and over will be subject to a 2% processing fee
 BANK INFO:
 BANK OF AMERICA
 601 S Rancho Santa Fe Rd, San Marcos, CA 92078
 Account #: 001138801359
 Swift Code: BOFAUS3N
 Bank Routing #: 026009593 (Wire)
 Bank Routing #: 121000358 (ACH)

Subtotal	33,107.00
Estimated Shipping Cost (Freight Forwarder)	0.00
Estimated Tax	1,986.42
Total	\$35,093.42