

Water Supply and/or Sewage Disposal System Construction Permit Page 1 of

Commonwealth of Virginia
Department of Health
GREENE CO. HEALTH DEPARTMENT

Health Department
Identification Number: 139-98-0058
Tax Map Number: 50(A)14--25

General Information

Water Supply System: PUBLIC

Sewage Disposal System: REPAIR

Based on the application for a sewage disposal system construction permit filed in accordance with Section 2.13 E, of the Sewage Handling and Disposal Regulations and/or Section 2.13 of the Private Well Regulations a construction permit is hereby issued to:

Owner: VALLEY VIEW LAND TRUST C/O P. MORRIS

Telephone: 804-985-~~0058~~ 7694

Agent: RODNEY KIBLER Address: P.O. BOX 224, QUINQUE, VA 22965

For a Type I Sewage Disposal System or Well to be constructed on/at
RT 33 NEXT TO KINGDOM HALL

Sec/Bk Lot Actual or estimated water use 900 gpd - 6 bedrooms

DESIGN	NOTE: SEWAGE DISPOSAL SYSTEM INSPECTION RESULTS
Water supply, PUBLIC SUPPLY	Water supply location: Satisfactory yes <u> </u> no <u> </u>
	EHS <u> </u> DATE <u> </u>
Building Sewer: <u>4"</u> I.D. PVC Schedule 40, or equivalent. Slope 1.25" per 10ft (min.)	Building Sewer: Satisfactory yes <u> </u> no <u> </u>
Other <u> </u>	EHS <u> </u> DATE <u> </u>
Septic Tank: Capacity: <u>1800 Gals. (min.)</u>	Pretreatment unit: Satisfactory yes <u> </u> no <u> </u>
Other <u> </u>	EHS <u> </u> DATE <u> </u>
Inlet-outlet structure: PVC Schedule 40, 4" tees or equivalent.	Inlet-outlet structure: Satisfactory yes <u> </u> no <u> </u>
Other <u> </u>	EHS <u> </u> DATE <u> </u>
Pump and pump station: <u>NO</u>	Pump & pump station: Satisfactory yes <u> </u> no <u> </u>
	EHS <u> </u> DATE <u> </u>
Gravity mains: 3" or larger I.D., min. 6" fall per 100 ft., 1500 lb. crush strength or equivalent. Other <u> </u>	Conveyance method: Satisfactory yes <u> </u> no <u> </u>
	EHS <u> </u> DATE <u> </u>
Distribution Box: Precast concrete with <u>10</u> ports.	Distribution box: Satisfactory yes <u> </u> no <u> </u>
Other <u> </u>	EHS <u> </u> DATE <u> </u>
Header lines: Material: 4" I.D. 1500 lb. crush strength plastic or equivalent from distribution box to 2 ft into absorption trench. Slope 2" min. Other <u> </u>	Header lines: Satisfactory yes <u> </u> no <u> </u>
	EHS <u> </u> DATE <u> </u>
Percolation lines: Gravity 4" plastic 1000 lb. per foot bearing load or equiv. slope 2" - 4" (min. max.) per 100ft	Percolation lines: Satisfactory yes <u> </u> no <u> </u>
Other <u> </u>	EHS <u> </u> DATE <u> </u>
Absorption trenches: Sq ft. required: <u>2160</u> depth from ground surface to bottom of trench <u>60"</u> : aggregate size <u>.5-1.5"</u> : Trench bottom slope <u>2-4"/100 ft</u> center to center spacing <u>9 FT</u> : Trench width <u>36"</u> Depth of aggregate <u>13"</u> : Trench length <u>80 ft</u> : Number of trenches <u>9</u> :	Absorption trenches: Satisfactory yes <u> </u> no <u> </u>
	EHS <u> </u> DATE <u> </u>
	Date <u> </u> Approved by: <u> </u> Environmental Health Specialists


Schematic drawing of sewage disposal and/or water supply system and topographic features.

Show the lot lines of the building site, sketch of property showing any topographic features which may impact on the design of the well or sewage disposal system, including existing and/or proposed structures and sewage disposal systems and wells within 200 feet. The schematic drawing of the well site or area and/or sewage disposal system shall show sewer lines, pretreatment unit, pump station, conveyance system, and subsurface soil absorption system, reserve area, etc. When a nonpublic drinking water supply is to be permitted, show all sources of pollution within 200 feet.

☐ The information required above has been drawn on the attached copy of the sketch submitted with the application.

DRAWING NOT TO SCALE

OUTER TRENCHES OPEN FOR INSPECTION
INNER TRENCHES 3-4 INSPECTION POINTS
DO NOT ATTEMPT TO INSTALL DRAINFIELD
DURING PERIODS OF INCLEMENT WEATHER



This sewage disposal system and/or water supply is to be constructed as specified by this permit.

This sewage disposal system and/or well construction permit is null and void if (a) conditions are changed from those shown on the application (b) conditions are changed from those shown on the construction permit.

No part of any installation shall be covered or used until inspected, corrections made if necessary, and approved, by the local health department or unless expressly authorized by the local health dept. Any part of any installation which has been covered prior to approval shall be uncovered, if necessary, upon the direction of the Department.

Date: 4/15/98 Issued by: R. C. Nul
Environmental Health Specialist

Date: _____ Reviewed by: _____
Environmental Health Supervisor

This Construction
Permit Valid until
10/15/98

Page 3 of 3

Health Department Identification Number: 139 98 0058

Tax Map Number: 50(A)14--25

- * See page #3 for design drawing. This drawing is not to scale!
- * Basement (floor is below surface of ground)? YES NO Walkout YES NO
- * Fixtures in basement? YES NO If yes, is a lift pump required? YES NO
- * Pump is required when the ground surface over the drainfield trenches is at a higher elevation than any plumbing fixture or the sewer line leaving the house.
- * Do not disturb the drainfield or reserve area(s).
- * Permit is void if the house location interferes with the proposed well or drainfield/reserve locations.
- * No buried utility service shall be closer than 10' to any part of this system.
- * Follow all OSHA requirements
- * Do not install drainfield system during periods of wet weather or wet soil.
- * It is recommended that all trees be removed from the drainfield area and all hydrophilic trees within 10' of the drainfield area MUST be removed.
- * Placed untreated building paper or approved material over the trench gravel.
- * The maximum soil cover over septic/pump tanks and distribution boxes is 18" to 24".
- * All tanks shall be watertight.
- * Final grade of drainfield shall be crowned to divert surface water & prevent ponding.
- * Roof drains, basement sump discharges (non-sewage), floor drains, footing drains, discharge from water treatment systems, etc. being connected to this system is PROHIBITED! Divert these away from drainfield.
- * Keep structures & driveways off drainfield/reserve area(s).
- * Minimum separation between drainfield/reserve area(s) & well sites is 100' for Class IIC wells & 50' for Class IIB wells. This distance increases by 25' for every 5% of slope for wells down slope of any source of contamination (house site, drainfield/reserve areas, etc).
- * It is the owner's responsibility to ensure that the well and septic system is on the property & does not interfere with utilities and easements.
- * Well & all water lines shall be disinfected prior to water sampling.
- * Health Dept. Operation Permit & Well Inspection Report required prior to occupancy.
- * It shall be the responsibility of owner or any subsequent owner to maintain, repair or replace (requires a permit) any sewage disposal system that ceases to operated in a sanitary manner.
- * All septic and well contractors must have a current license with the Va. Dept. of Commerce.
- * Dry holes must be permanently abandoned in accordance with the Private Well Regulations.
- * Is septic tank location in a place of suspected high water table? YES NO If yes, please refer to tank manufacturer's instructions on placing tanks in saturated areas.
- * It is illegal to put either well or septic system into use without final Health Department approval.

Commonwealth of Virginia

Application for a Sewage Disposal and/or Water Supply Permit

Health Department ID 139 98 0058

Mail to PO Box 224
Quinque VA 22965

To Be Completed By The Applicant

Type of sewage system: New ☒ Repair Expanded Conditional

FHA/VA yes no Case No. 985-7694

Owner Rodney Kibler Address PO Box 224 Phone 985-7694
Stanardsville VA

Agent Address Phone

Directions of Property Quinque (near Julius Morris)

Subdivision Section Block Lot

Other Property Identification Rt 33 next to Kingdom Hall

Dimension/size of Lot/Property

Other Application Information

I. Building/facility New Existing ☒
Intermittent Use ☒ Yes No If yes, describe

II. Residential Use Yes No
Termite Treatment ☒ Yes No
 Single Family Multi-family
(Number of Bedrooms) (Number of Units 2)

Basement Yes No
Fixtures in Basement ☒ Yes No

III. Commerical Use Yes No Describe:

Commerical/Wastewater Yes ☒ No Number of Patrons
Number of Employees

If yes, give volumes and describe

IV. Water Supply: Public New Existing
 Private New Existing

Describe:

V. Proposed Sewage Disposal Method:

Onsite Sewage Disposal System: ☒ Septic Tank Drainfield LPD Mound Other

Public Sewerage System

Attach a site plan (rough sketch) showing dimensions of property, proposed and/or existing structures and driveways, underground utilities, adjacent soil absorption system, bodies of water, drainage ways, and wells and springs within 200 feet radius of the center of the proposed well or drainfield. Distances may be paced or estimated.

The property lines and building location are clearly marked and the property is sufficiently visible to see the topography. I give permission to the Department to enter onto the property described for the purpose of processing this application.

Signature of Owner/Agent Rodney Kibler

Date 3/3/98

DATE: 4/7/92

ASSIGNED TO: Roger Nelson

OWNER'S NAME: VALLEY VIEW LAND TRUST C/O P. MORRIS

SYSTEM TYPE: F

DIRECTIONS:

WELL TYPE: W44C

TRENCH DEPTH: 60"

OF TRENCHES: 9

DEPTH TO ROCK: N/A

LENGTH: 80

DEPTH TO WATER TABLE: 2 1/2

CENTERS: 62

DEPTH TO FREE WATER: *uh*

SLOPE: 13°0 / LANDSCAPE: SIDE SLOPE

TEXTURE GROUP: TC

PERK RATE: 43

MAIL TO:

[illegible]

SIGNATURE OF EVALUATOR: B. C. N. L.

RECORD OF INSPECTION-SEWAGE DISPOSAL SYSTEM

33-2

Date 11/1/80 Case No. _____
 Owner Julius Morris Address Stanardsville, Va Phone _____
 (Mailing Address)
 Occupant Per Rent Address _____ Phone _____
 (Mailing Address)
 Exact Location of Premises to the west of Rt. 33 ABOUT 0.1 mi west of Rt. 633
 (Subdivision, Street or Road Name, Section or Lot No.)

WATER SUPPLY INSPECTION

Installed according to Permit Design ☒ Yes ☐ No. Distance to nearest House Sewer 50+ feet. Distance to nearest Sewage Disposal System 100+ feet. (Use Form LHS-143 for Detailed Inspection of Water Supply Reference Materials.)

SEWAGE DISPOSAL SYSTEM INSPECTION

- (1) LOCATION
 Allotted Area adequate ☒ Yes ☐ No. Distance from nearest lot lines 5+ feet. Trees none feet. Water Supplies 100+ feet. Buildings none feet.
- (2) INSTALLATION AND DESIGN
 Installed according to Permit Design ☒ Yes ☐ No.
 Have additional Household Appliances been added NOT on Permit Y/N
☐ Automatic Washer ☐ Garbage Disposal
☐ Other _____ (Describe)
- (3) SOIL CONDITION
 Are there soil conditions now evident which indicate system may be unsatisfactory as designed: ☐ Yes ☒ No. If Yes, show adjustments required under "Remarks" below.
- (4) HOUSE SEWER LINE
 Installed ☐ Yes ☒ No. Type of material _____ Size _____ Inches.
- (5) SEPTIC TANK
 Constructed of concrete (1000 gal)
 Inside Dimensions Length 8 feet. Width 4 feet. Liquid Depth 4 feet. Depth of Air Space 1 inches. Inside Fittings comply with requirements ☒ Yes ☐ No.
- (6) DISTRIBUTION BOX
 Watertight and equal surcharge to each line by Water Test ☒ Yes ☐ No. Distribution Box provided with 5 extra outlets for future use. (Number)
- (7) SUBSURFACE ABSORPTION FIELD
 Total Area in bottom of ditches 1200 square feet. Number of ditches 4 Length of ditches 100x3 feet. Grade of ditches Minimum 2 inches per 100 feet. Maximum 6 inches per 100 feet. Has system been checked by instruments (Level) ☒ Yes ☐ No. Type aggregate used gravel
 Depth of aggregate under Tile 6 inches
 Total depth of aggregate 15 inches
 Depth of backfill over aggregate 30 inches
- (8) SURFACE DRAINAGE
 Storm Drains from House and Basement flowing away from Subsurface Drainage Field: ☐ Yes ☒ No. Was Surface Drainage required ☐ Yes ☒ No. If Yes, has this been provided ☐ Yes ☐ No. Has area been drained by lowering Ground Water Table: ☐ Yes ☐ No. ☒ Not required.
- (9) Are follow-up inspections necessary ☐ Yes ☒ No.

Septic Tank Contractor: Earl Shifflett Address Stanardsville, Va Phone _____
 This Sewage Disposal System (Is) ☒ Approved by Greener, G Health Department
 Date 11/1/80 Signed W. H. Crow (Sanitarian)
 Date _____ Approved _____ (Reviewing Authority)

With proper maintenance, approved Sewage Disposal systems may be expected to function satisfactorily, provided no overloading or physical damage occurs to the system. Remarks: _____

PERMIT TO INSTALL ☒ REPAIR, ☐ REASONS FOR REJECTION ☐ WATER SUPPLY ☐ SEWAGE DISPOSAL SYSTEM ☒

(1) Void after (12) twelve months. (2) Automatically cancelled when site conditions are changed from those shown on permit.
 (3) Automatically cancelled should facts later become known that a potential hazard would be created by continuing installation.

FHA/VA ☐ Yes ☒ No Date 11/1/80 Case No. _____

Owner Julius Morris Address Standards, Va Phone _____
 (Mailing Address)

Occupant for rent Address _____ Phone _____
 (Mailing Address)

Exact Location of premises to the north of Rt. 33 ABOUT 0.1 mi west of Rt. 633
 (Subdivision, Street or Road Name, Section or Lot No.)

FOR: ☒ Dwelling ☒ Other office Automatic Washing Machine ☐ Yes ☒ No Consumption 200 gal. per day
 Actual ☐ Potential ☐ Bedrooms _____ Garbage Disposal Unit ☐ Yes ☒ No (☐ Actual ☒ Estimated Water)
 Additional wastes none

(1) WATER SUPPLY (Existing) Class _____ Approved ☐ Yes ☐ No Other well
 (To be installed) Class 1 1/2 Cased 1 1/2 ft. to be grouted 1 1/2 ft.

(Unless supported by positive evidence Class III is to be considered as to be installed.)

(2) SOIL STUDY Naturally drained, suitable by sight ☒ Yes ☐ No Technical Classification UNKNOWN
 (If Known)
 Estimated Percolation Rate 1-10 ☐ 11-25 ☐ 26-50 ☐ > 51 ☒ Percolation Test Required ☐ Yes ☒ No Rate _____
 (Minutes per inch) (Minutes per inch to nearest 10 minutes)
 Depth to Grey Mottles > 60 inches (estimate over 4 ft.) OTHER None
 Surface drainage required ☐ Yes ☒ No OTHER DRAINAGE _____

(3) HOUSE SEWER LINE Size 4 inches. Type of material required PVC Distance from Water Supply 50+ feet.


(4) DETAILS OF CONSTRUCTION Watertight Septic Tank of concrete Material Liquid Capacity 750 gallons.
 Inside Dimensions Length 7 feet. Width 3.6 feet. Liquid Depth 4.0 feet. Depth of Air Space 1.0 feet.

SUBSURFACE ABSORPTION FIELD Number of square feet required 600 Type aggregate required gravel

(5) Depth of aggregate from base of tile to bottom of ditches 6 inches. Allowable fall 2 to 6 inches.
 Total aggregate minimum depth 12 inches or more. Depth of drainfield to be 40 inches from surface of original ground.

Distance from well to septic tank 50+ feet; distance from well to drainfield KUT feet. MIN TO ALL INDIV. WATER SUPPLIES

Rough Sketch of Premises (including adjacent properties if pertinent, Showing Location of Lot Line, Buildings, Water Supplies, Sewage Disposal Systems, Trees, and Other Possible Sources of Contamination of Water Supplies, by Indicating Distances and Slope with regard to one another.



Note: Owner or his agent must notify Krene G Health Department, Phone 955-2163 when installation is ready for inspection. If any Sewage Disposal System, or part thereof, is covered before being inspected by the Health Department, it shall be uncovered at the direction of the Health Director or his agent. CONDITIONS DISCOVERED DURING INSTALLATION MAY REQUIRE ADJUSTMENTS OF SYSTEM DESIGN. Changes from above specifications require Health Department approval before being made.

Based on the above information, the undersigned recommends that this permit be issued. Date 11/1/80 Signed C. A. Cras
 (Reviewing Authority) (Sanitarian or Health Director)

GREENE COUNTY HEALTH DEPARTMENT
STANARDSVILLE, VIRGINIA

IN COOPERATION WITH THE
STATE DEPARTMENT OF HEALTH

TO: James G. Dept. Jorring
FROM: GREENE COUNTY HEALTH DEPARTMENT
DATE: Nov 21, 1989
SUBJECT: Change of use of Building

D.B.# _____ TAXMAP # _____ PARCEL # _____

OWNER Reuben D. Kibler Ph.D.

SUBDIVISION _____ LOT# _____ BLOCK _____ SECT. _____

GENERAL LOCATION North of Rt 33 about 0.1 mile
west of Rt 633

TRAILER PARK _____ LOT# _____

PERSON CONTACTED, IF BY PHONE _____



THIS IS TO INFORM YOUR DEPARTMENT THET THE EXISTING SYSTEM
IS ADEQUATE FOR THE PROPOSED USE.



OTHER Proposed use will not include more
than 6 occupants and will have no
more than 3 bedrooms per letter from
Mr Kibler (enclosed)

Dwayne Z. Miller
Environmental Health Specialist

GREENE COUNTY HEALTH DEPARTMENT
STANARDSVILLE, VIRGINIA

IN COOPERATION WITH THE
STATE DEPARTMENT OF HEALTH

MEMORANDUM

TO: RUCKEAVILLE CONGREGATION OF JEHOVAN'S WITNESSES
800 NORMAN LANE
EARLYSVILLE VA 22936

FROM: Dwight E. Hight, Sanitarian
Greene County Health Department

OWNER: _____

The soil at 3.01 acre parcel
located at North west intersection of Rt 33 and
633
appears to be suitable for the placement of subsurface drainfields. These findings are based on soils studies conducted by myself or a soil scientist under my supervision.

The lot sizes are such that there appears to be enough area to install the required amount of drainfield for an average size dwelling, plus any reserve area required by section 8.06 of the Commonwealth of Virginia State Board of Health Sewage Handling and Disposal Regulations.


However, each lot will be evaluated on its own merit, and further tests may be required at the time the septic permit is applied for. Issuance or denial of the permit can be based on these tests.

Copies of these preliminary soil studies are on file at the Greene County Health Department showing proposed drainfield sites, house sites, and well sites if applicable. No change to these sites are to be made without prior approval from the appropriate authorities. No work is to be started without prior approval from the appropriate authorities.

REMARKS: perc Rate 22 requiring 1800 square feet of
drainfield. Enough for above congregation of
200 and a 2 bedroom apartment

Based on Perc Rate obtained from report
by E.O. Gooch and assoc. OWNER with
RETURN COPY of RESULTS.

DEED BOOK 111 PAGE 132
PROD.



PLAT OF 3 PARCELS OF LAND
LOCATED AT QUINQUE. SURVEYED
FROM THE LAND OF RODNEY KIBLER
FOR RUCKERSVILLE CONGREGATION
OF JEHOVAH'S WITNESSES.
SURVEYED NOVEMBER 25, 1989

ACCURATE

LAND SURVEYING COMPANY

Phone: (804) 448-3708

(804)798-4728

Ladysmith, Va. 22501

REF: WILLY DD634 6