



GLOBAL POSITION SYSTEM SURVEY NOTES

- The survey portion was performed using the following global positioning system (GPS) survey equipment: TOPCON Hyper Plus (Dual frequency). The GPS portion of this survey was performed using RTK (Real-Time Kinematic) surveying methods. TDOT CORS station TN38 for horizontal and for vertical control.
- The relative positional accuracy is stated in the Category "IV" survey certification located above the surveyor's seal on this drawing.
- The dates that fieldwork was performed for this survey were: October 2023.
- The datum(s) for the TDOT CORS Station that was used: HORIZ.: NAD83(2011) EPOCH 2010
VERT.: NAVD 1988
- Fixed Control Station designation with positional data:
TDOT CORS STATION-TN38
STATE PLANE (TN 4100-US SURVEY FT.)- NORTHING: 569,154.86
EASTING: 1,837,086.15
ELEVATION: 558.34 FT.
- Geoid model used- GEOID03
- Combined grid factors for TDOT CORS Station TN38:
0.99992680 (STATE PLANE-TN 4100-US SURVEY FT.)




- NOTES**
- In Tennessee, it is a requirement per "The Underground Utility Damage Prevention Act" that anyone who engages in excavation must notify all known underground utility owners, no less than three nor more than ten working days of their intent to excavate. A list of these utilities may be obtained from the County Register of Deeds. Those utilities that participate in the Tennessee One Call system can be notified by calling toll free 1-800-351-1111.
 - Underground utilities shown were located using available above ground evidence, as well as information obtained from the respective utility companies. The existence or nonexistence of the utilities shown and any other utilities which may be present on this site or adjacent sites should be confirmed with the utility owner prior to commencing any work.
 - It is the responsibility of each residential builder to design and construct a suitable grading and drainage scheme which will convey surface water, without ponding in the lot or under the house, from his structure to the drainage system constructed by the subdivision developer.
 - Parcels may be subject to additional easements, and/or restrictions, by record or prescription, that a complete title search may reveal.



LEGEND

- IPS O IRON PIN SET (1/2" REBAR WITH STAMPED PLASTIC CAP-H/S ENGR.)
- IPF O IRON PIN FND.
- SURVEY POINT
- ⊕ EXISTING ELECTRIC POLE
- EXISTING ELECTRIC LINE
- EXISTING FENCE



5 TRACTS - 25.05 Ac.±
0 100 200

THIS PARCEL IS NOT INCLUDED IN AREAS DESIGNATED AS SPECIAL FLOOD HAZARD ON THE NATIONAL FLOOD INSURANCE PROGRAM MAP NUMBER 420149C0225J DATED: MAY 9, 2023 ZONE: X MAP NUMBER 420149C02265J DATED: JAN. 5, 2007 ZONE: X

LINE	BEARING	LENGTH
L1	N7°31'17"E	31.04'

CURVE	DELTA	RADIUS	ARC	CHORD	BEARING
C1	18°52'30"	500.00'	164.72'	163.97'	N11°29'26"W
C2	8°31'54"	500.00'	74.45'	74.38'	S21°2'46"W
C3	2°24'04"	2970.00'	124.47'	124.46'	N8°42'19"E
C4	4°43'11"	1462.00'	120.43'	120.40'	N9°51'54"E

I HEREBY CERTIFY THAT THIS IS A CATEGORY "IV" SURVEY AND THE PRECISION OF THE GPS PORTION OF THIS SURVEY (IN RELATIVE POSITIONING ACCURACY GIVEN AT THE 95% CONFIDENCE LEVEL) IS 1:10,000 AS SHOWN HEREON AND THAT THIS SURVEY WAS DONE IN COMPLIANCE WITH CURRENT TENNESSEE MINIMUM STANDARDS OF PRACTICE FOR LAND SURVEYORS.

OWNER: THE ESTATE OF HELEN T. SMITH
ADDRESS: 1167 RUCKER LANE
MURFREESBORO, TN 37128
TAX MAP: 115, PART OF PARCEL: 18.00
PART OF WILL BOOK: 80, PAGE: 181
NOTE: THIS PARCEL IS SUBJECT TO ALL EASEMENTS AS SHOWN AND ANY OTHER EASEMENTS AND/OR RESTRICTIONS EITHER RECORDED OR BY PRESCRIPTION THAT A COMPLETE TITLE SEARCH MAY REVEAL.

H. HUDDLESTON-STEEL ENGINEERING, INC.
2115 N.W. BROAD STREET, MURFREESBORO, TN 37129
SURVEYING : 893 - 4084, FAX: 893 - 0080

AUCTION PLAT
THE ESTATE OF HELEN T. SMITH
12th CIVIL DISTRICT - RUTHERFORD COUNTY - TN.
DATE: OCTOBER 2023 SCALE: 1"=100' SH. 1 OF 1