

4000 Roofing

Roofing OC Duration

Remove all existing asphalt shingles.
Remove underlayment.
Remove all existing accessories.
Remove all box vents and cover current openings.
Install new drip edge.
Install new ice and water on valleys.
Install new starter strip.
Install new architectural shingle.
Install new accessories.
Install new ventilation.

PD
PAID In Full
NEW ROOFING
\$12,800.00 Ch # 4570
5/11/2023

For color, specs and warranty information please follow the link below.

Color(s) and Specs: <https://www.owenscorning.com/en-us/roofing/shingles>

Warranty: <https://www.owenscorning.com/en-us/roofing/warranty>

Tear Off	29.27 each
Rhino Synthetic 10sq/roll	3 each
Ice and water	1 each
1 1/2 Drip Edge	31 each
Owens Corning - Starter Strip plus	3 each
Owens Corning - Duration - Designer Color	32 square
Owens Corning Proedge	3 each
1 1/4 Coil Nail	2 box
1" Plastic Cap 2000ct	2 each
Lomanco 4' Omni	10 each
Roofing Labor - sub contract up to 8/12	33 square
Dump - Roofing	1 each
3" Lead Boot	2 each
NP1	5 each
Aluminum Coil	1 each
Step Flashing - 5"x7"	1 each

Base Price

\$12,800.00