

DEPARTMENT OF THE ARMY PERMIT

Permittee: MR. KENNETH DEESE
HIGH TIDE RV RESORT, LLC
3574 TRAVELERS REST ROAD
NEWTON, GEORGIA 39870

Permit No: SAJ-2005-02601(SP-TLW)

Issuing Office: U.S. Army Engineer District, Jacksonville

NOTE: The term "you" and its derivatives, as used in this permit, means the permittee or any future transferee. The term "this office" refers to the appropriate district or division office of the U.S. Army Corps of Engineers (Corps) having jurisdiction over the permitted activity or the appropriate official of that office acting under the authority of the commanding officer.

You are authorized to perform work in accordance with the terms and conditions specified below.

Project Description: The permittee is authorized to conduct maintenance excavation in a 318 feet (ft.) by 67 ft. canal, removing 4,240 cubic yards of material, to install 345 linear ft. of seawall approximately 1 ft. waterward of the mean high water line (mhw), and to install 76 ft. of riprap approximately 5 ft. waterward of mhw. The applicant is also authorized to construct a 24 slip multi-family dock that consists of a 6 ft. x 4 ft. stationary platform and a 254 ft. x 4 ft. floating dock, (12) 3 ft. by 12 ft. finger piers, and (1) 4 ft. by 20 ft. finger pier for a total of 1,556 square ft. Excavated material will be placed on high ground and allowed to dry before being used as backfill for the seawall. No return water will be allowed to enter jurisdictional waters. The work described above is to be completed in accordance with the 9 pages of drawings and 6 attachments affixed at the end of this permit instrument.

Project Location: The project area is located at the intersection of Kornegay Way and Canal Street and will affect waters of the United States associated with an unnamed canal directly connected to the Gulf of Mexico. The project site is located in Section 121, Township 60 North, Range 60 East, Crawfordville, Wakulla County, Florida.

Directions to site: From Panama City, take Highway 213 North for 24 miles. Turn right onto Florida Highway 20 East. Drive east for 50 miles and turn right on Florida 267 South. Drive south for 21 miles. Take a left on Spring Creek Highway. In approximately 9 miles, turn left onto Shell Point Road. Stay on Shell Point Road for approximately 3 miles and then turn right onto Kornegay Way. The project area is located at the intersection of Kornegay Way and Canal Street.

PERMIT NUMBER: SAJ-2005-02601
PERMITTEE: Kenneth Deese
PAGE 2 of 12

Approximate Central Coordinates: Latitude: 30.073905 North
Longitude: -84.300765 West

Permit Conditions

General Conditions:

1. The time limit for completing the work authorized ends on December 14, 2028. If you find that you need more time to complete the authorized activity, submit your request for a time extension to this office for consideration at least one month before the above date is reached.
2. You must maintain the activity authorized by this permit in good condition and in conformance with the terms and conditions of this permit. You are not relieved of this requirement if you abandon the permitted activity, although you may make a good faith transfer to a third party in compliance with General Condition 4 below. Should you wish to cease to maintain the authorized activity or should you desire to abandon it without a good faith transfer, you must obtain a modification of this permit from this office, which may require restoration of the area.
3. If you discover any previously unknown historic or archeological remains while accomplishing the activity authorized by this permit, you must immediately notify this office of what you have found. We will initiate the Federal and State coordination required to determine if the remains warrant a recovery effort or if the site is eligible for listing in the National Register of Historic Places.
4. If you sell the property associated with this permit, you must obtain the signature and the mailing address of the new owner in the space provided and forward a copy of the permit to this office to validate the transfer of this authorization.
5. If a conditioned water quality certification has been issued for your project, you must comply with the conditions specified in the certification as special conditions to this permit. For your convenience, a copy of the certification is attached if it contains such conditions (Attachment 5).
6. You must allow representatives from this office to inspect the authorized activity at any time deemed necessary to ensure that it is being or has been accomplished in accordance with the terms and conditions of your permit.

PERMIT NUMBER: SAJ-2005-02601
PERMITTEE: Kenneth Deese
PAGE 3 of 12

Special Conditions:

1. Reporting Address: The Permittee shall submit all reports, notifications, documentation, and correspondence required by the general and special conditions of this permit to either (not both) of the following addresses:

a. For electronic mail (preferred): SAJ-RD-Enforcement@usace.army.mil (not to exceed 15 MB).

b. For standard mail: U.S. Army Corps of Engineers, Regulatory Division, Enforcement Section, P.O. Box 4970, Jacksonville, FL 32232-0019.

The Permittee shall reference this permit number, SAJ-2005-02601(SP - TLW), on all submittals.

2. Commencement Notification: Within 10 days from the date of initiating the work authorized by this permit, the Permittee shall submit a completed "Commencement Notification" form (Attachment 1).

3. As-Built Certification: Within 60 days of completion of the work authorized by this permit, the Permittee shall submit as-built drawings of the authorized work and a completed "As-Built Certification By Professional Engineer" form (Attachment 2) to the Corps. The as-built drawings shall be signed and sealed by a registered professional engineer and include the following:

a. A plan view drawing of the location of the authorized work footprint, as shown on the permit drawings, with an overlay of the work as constructed. The plan view drawing should show all existing water management structures and the completed structures, dredge/fill activities, and wetland impacts.

b. A list of any deviations between the work authorized by this permit and the work as constructed. In the event that the completed work deviates, in any manner, from the authorized work, describe on the attached "As-Built Certification By Professional Engineer" form the deviations between the work authorized by this permit and the work as constructed. Clearly indicate on the as-built drawings any deviations that have been listed. Please note that the depiction and/or description of any deviations on the drawings and/or "As-Built Certification By Professional Engineer" form does not constitute approval of any deviations by the Corps.

c. Include the Department of the Army permit number on all sheets submitted.

PERMIT NUMBER: SAJ-2005-02601
PERMITTEE: Kenneth Deese
PAGE 4 of 12

4. Agency Changes/Approvals: Should any other agency require and/or approve changes to the work authorized or obligated by this permit, the Permittee is advised a modification to this permit instrument is required prior to initiation of those changes. It is the Permittee's responsibility to request a modification of this permit from the Panama City Permits Section. The Corps reserves the right to fully evaluate, amend, and approve or deny the request for modification of this permit.

5. Permit Conditions Prevail: If information in the permit attachments conflict with the special conditions of this permit, the requirements of the permit special conditions shall prevail.

6. Posting of Permit: The Permittee shall have available and maintain for review a copy of this permit and approved plans at the construction site.

7. Cultural Resources/Historic Properties:

a. No structure or work shall adversely affect impact or disturb properties listed in the National Register of Historic Places (NRHP) or those eligible for inclusion in the NRHP.

b. If, during the ground disturbing activities and construction work within the permit area, there are archaeological/cultural materials encountered which were not the subject of a previous cultural resources assessment survey (and which shall include, but not be limited to: pottery, modified shell, human remains, ceramics, stone tools or metal implements, dugout canoes, evidence of structures or any other physical remains that could be associated with native cultures or early colonial settlement), the Permittee shall immediately stop all work and ground-disturbing activities within a 100-meter diameter of the discovery and notify the Corps at the addresses listed in the Reporting Address Special Condition within the same business day (8 hours). The Corps shall coordinate with the Florida State Historic Preservation Officer (SHPO) to assess the significance of the discovery and devise appropriate actions.

c. Additional cultural resources assessments may be required of the permit area in the case of unanticipated discoveries as referenced in accordance with the above Special Condition and if deemed necessary by the SHPO, or Corps, in accordance with 36 CFR 800 or 33 CFR 325, Appendix C (5). Based, on the circumstances of the discovery, equity to all parties, and considerations of the public interest, the Corps may modify, suspend or revoke the permit in accordance with 33 CFR Part 325.7. Such activity shall not resume on non-federal lands without written authorization from the SHPO for finds under his or her jurisdiction, and from the Corps.

d. In the unlikely event that unmarked human remains are identified on non-federal lands, they will be treated in accordance with Section 872.05 Florida Statutes. All work and ground disturbing activities within a 100-meter diameter of the unmarked human remains shall immediately cease and the Permittee shall immediately notify the medical examiner, Corps, and State Archeologist within the same business day (8-hours). The Corps shall then notify the appropriate SHPO. Based, on the circumstances of the discovery, equity to all parties, and considerations of the public interest, the Corps may modify, suspend or revoke the permit in accordance with 33 CFR Part 325.7. Such activity shall not resume without written authorization from the SHPO and from the Corps.

e. If prehistoric or historic artifacts such as pottery or ceramics, projectile points, dugout canoes, metal implements, historic building materials, or any other physical remains that could be associated with Native American, early European, or American settlement are encountered at any time within the project site area, the permitted project shall cease all activities involving subsurface disturbance in the vicinity of the discovery. The applicant shall contact the Florida Department of State, Division of Historical Resources, Compliance Review Section at (850)-245-6333. Project activities shall not resume without verbal and/or written authorization. In the event that unmarked human remains are encountered during permitted activities, all work shall stop immediately and the proper authorities notified in accordance with Section 872.05, Florida Statutes.

8. Turbidity Barriers: Prior to the initiation of any of the work authorized by this permit, the Permittee shall install floating turbidity barriers with weighted skirts that extend to within 1 foot from bottom of the bottom around all work areas that are in, or adjacent to, surface waters. The turbidity barriers shall remain in place and be maintained until the authorized work has been completed and all suspended and erodible materials have been stabilized. Turbidity barriers shall be removed upon stabilization of the work area.

9. Fill Material: The Permittee shall use only clean fill material for this project. The fill material shall be free from items such as trash, debris, automotive parts, asphalt, construction materials, concrete block with exposed reinforcement bars, and soils contaminated with any toxic substance, in toxic amounts in accordance with Section 307 of the Clean Water Act.

10. Manatee Conditions: The Permittee shall comply with the "Standard Manatee Conditions for In-Water Work – 2011" (Attachment 3).

11. Jacksonville District Programmatic Biological Opinion (JAXBO): Structures and activities authorized under this permit will be constructed and operated in

PERMIT NUMBER: SAJ-2005-02601
PERMITTEE: Kenneth Deese
PAGE 6 of 12

accordance with all applicable PDCs contained in the JAXBO, based on the permitted activity. Johnson's seagrass and its critical habitat were delisted from the Endangered Species Act on May 16, 2022. Therefore, JAXBO PDCs required to minimize adverse effects to Johnson's seagrass and its critical habitat are no longer applicable to any project. Failure to comply with applicable PDCs will constitute noncompliance with this permit. In addition, failure to comply with the applicable PDCs, where a take of listed species occurs, would constitute an unauthorized take. The NMFS is the appropriate authority to determine compliance with the Endangered Species Act. The most current version of JAXBO can be accessed at the Jacksonville District Regulatory Division website in the Endangered Species section of the Sourcebook located at: <http://www.saj.usace.army.mil/Missions/Regulatory/SourceBook.aspx>

JAXBO may be subject to revision at any time. The most recent version of the JAXBO must be utilized during the design and construction of the permitted work.

12. Assurance of Navigation and Maintenance: The Permittee understands and agrees that, if future operations by the United States require the removal, relocation, or other alteration, of the structures or work herein authorized, or if in the opinion of the Secretary of the Army or his authorized representative, said structure or work shall cause unreasonable obstruction to the free navigation of the navigable waters, the Permittee will be required, upon due notice from the U.S. Army Corps of Engineers, to remove, relocate, or alter the structural work or obstructions caused thereby, without expense to the United States. No claim shall be made against the United States on account of any such removal or alteration.

13. Eastern Indigo Snake Protection Measures and Inspection: Permittee shall comply with U.S. Fish and Wildlife Service's "Standard Protection Measures for the Eastern Indigo Snake" dated March 23, 2021, as provided in Attachment 4 of this permit. All gopher tortoise burrows, active or inactive, shall be evacuated prior to site manipulation in the vicinity of the burrow. If excavating potentially occupied burrows, active or inactive, individuals must first obtain state authorization via a Florida Fish and Wildlife Conservation Commission (FWC) Authorized Gopher Tortoise Agent permit. The excavation method selected shall minimize the potential for injury of an indigo snake. The Permittee shall follow the excavation guidance provided in the most current FWC Gopher Tortoise Permitting Guidelines found at <http://myfwc.com/gophertortoise>. If an indigo snake is encountered, the snake must be allowed to vacate the area prior to additional site manipulation in the vicinity. Holes, cavities, and snake refugia other than gopher tortoise burrows shall be inspected each morning before planned site manipulation of a particular area, and if occupied by an indigo snake, no work shall commence until the snake has vacated the vicinity of the proposed work.

PERMIT NUMBER: SAJ-2005-02601
PERMITTEE: Kenneth Deese
PAGE 7 of 12

14. Dredged Material Disposal: The Permittee shall place all dredged material in a self-contained, upland disposal site. The Permittee shall maintain the upland disposal site to prevent the discharge of dredged material and associated effluent into waters of the United States.

15. Pre-Construction Meeting: The Permittee will schedule a pre-construction meeting with a Corps representative no later than 30 days prior to the start of work to review the special conditions of the permit. The Permittee shall not start work prior to the pre-construction meeting.

Further Information:

1. Congressional Authorities: You have been authorized to undertake the activity described above pursuant to:

(X) Section 10 of the Rivers and Harbors Act of 1899 (33 U.S.C. 403)

(X) Section 404 of the Clean Water Act (33 U.S.C. 1344)

() Section 103 of the Marine Protection, Research and Sanctuaries Act of 1972 (33 U.S.C. 1413)

() Section 14 of the Rivers and Harbors Act of 1899 (33 U.S.C. 408)

2. Limits of this authorization.

a. This permit does not obviate the need to obtain other Federal, State, or local authorizations required by law.

b. This permit does not grant any property rights or exclusive privileges.

c. This permit does not authorize any injury to the property or rights of others.

d. This permit does not authorize interference with any existing or proposed Federal projects.

3. Limits of Federal Liability. In issuing this permit, the Federal Government does not assume any liability for the following:

PERMIT NUMBER: SAJ-2005-02601
PERMITTEE: Kenneth Deese
PAGE 8 of 12

a. Damages to the permitted project or uses thereof as a result of other permitted or unpermitted activities or from natural causes.

b. Damages to the permitted project or uses thereof as a result of current or future activities undertaken by or on behalf of the United States in the public interest.

c. Damages to persons, property, or to other permitted or unpermitted activities or structures caused by the activity authorized by this permit.

d. Design or construction deficiencies associated with the permitted work.

e. Damage claims associated with any future modification, suspension, or revocation of this permit.

4. Reliance on Applicant's Data: The determination of this office that issuance of this permit is not contrary to the public interest was made in reliance on the information you provided.

5. Reevaluation of Permit Decision: This office may reevaluate its decision on this permit at any time the circumstances warrant. Circumstances that could require a reevaluation include, but are not limited to, the following:

a. You fail to comply with the terms and conditions of this permit.

b. The information provided by you in support of your permit application proves to have been false, incomplete, or inaccurate (see 4 above).

c. Significant new information surfaces which this office did not consider in reaching the original public interest decision.

Such a reevaluation may result in a determination that it is appropriate to use the suspension, modification, and revocation procedures contained in 33 CFR 325.7 or enforcement procedures such as those contained in 33 CFR 326.4 and 326.5. The referenced enforcement procedures provide for the issuance of an administrative order requiring you comply with the terms and conditions of your permit and for the initiation of legal action where appropriate. You will be required to pay for any corrective measures ordered by this office, and if you fail to comply with such directive, this office may in certain situations (such as those specified in 33 CFR 209.170) accomplish the corrective measures by contract or otherwise and bill you for the cost.

PERMIT NUMBER: SAJ-2005-02601
PERMITTEE: Kenneth Deese
PAGE 9 of 12

6. Extensions: General Condition 1 establishes a time limit for the completion of the activity authorized by this permit. Unless there are circumstances requiring either a prompt completion of the authorized activity or a reevaluation of the public interest decision, the Corps will normally give favorable consideration to a request for an extension of this time limit.

PERMIT NUMBER: SAJ-2005-02601
PERMITTEE: Kenneth Deese
PAGE 10 of 12


Your signature below, as permittee, indicates that you accept and agree to comply with the terms and conditions of this permit.

Kenneth Deese
(PERMITTEE)

12/8/23
(DATE)

Kenneth Deese
(PERMITTEE NAME-PRINTED)

Tracy S. Wade



This permit becomes effective when the Federal official, designated to act for the Secretary of the Army, has signed below.

For

JAMES L. BOOTH
Colonel, U.S. Army
District Commander

Date: _____

PERMIT NUMBER: SAJ-2005-02601
PERMITTEE: Kenneth Deese
PAGE 11 of 12

When the structures or work authorized by this permit are still in existence at the time the property is transferred, the terms and conditions of this permit will continue to be binding on the new owner(s) of the property. To validate the transfer of this permit and the associated liabilities associated with compliance with its terms and conditions, have the transferee sign and date below.

(TRANSFEREE-SIGNATURE)

(DATE)

(NAME-PRINTED)

(ADDRESS)

(CITY, STATE, AND ZIP CODE)

PERMIT NUMBER: SAJ-2005-02601
PERMITTEE: Kenneth Deese
PAGE 12 of 12

***Attachments to Department of the Army
Permit Number SAJ-2005-02601***

1. COMMENCEMENT NOTICE: 1 page
2. AS-BUILT CERTIFICATION FORM: 2 pages
3. MANATEE CONDITIONS: 2 pages, *Standard Manatee Conditions for In-Water Work – 2011*
4. EASTERN INDIGO SNAKE CONDITIONS: 6 pages
5. WATER QUALITY CERTIFICATION: Specific Conditions of the water quality permit/certification in accordance with General Condition number 5 on page 2 of this DA permit. 24 pages.
6. PERMIT DRAWINGS: 9 pages, dated June 6, 2016

COMMENCEMENT NOTIFICATION

*Within ten (10) days of initiating the authorized work, submit this form to via electronic mail to saj-rd-enforcement@usace.army.mil (preferred, not to exceed 15 MB) **or** by standard mail to U.S. Army Corps of Engineers, Enforcement Section, P.O. Box 4970, Jacksonville, FL 32232-0019.*

1. Department of the Army Permit Number: SAJ-2005-02601(SP-TLW)

2. Permittee Information:

Name: _____

Email: _____

Address: _____

Phone: _____

3. Construction Start Date: _____

4. Contact to Schedule Inspection:

Name: _____

Email: _____

Phone: _____

Signature of Permittee

Printed Name of Permittee

Date

AS-BUILT CERTIFICATION BY PROFESSIONAL ENGINEER

Submit this form and one set of as-built engineering drawings to the U.S. Army Corps of Engineers, Enforcement Section, P.O. Box 4970, Jacksonville, FL 32232-0019. For electronic mail saj-rd-enforcement@usace.army.mil (not to exceed 15 MB).

1. Department of the Army Permit Number: SAJ-2005-02601(SP-TLW)

2. Permittee Information:

Name: _____

Address: _____

3. Project Site Identification (physical location/address):

4. As-Built Certification: I hereby certify that the authorized work, including any mitigation required by Special Conditions to the permit, has been accomplished in accordance with the Department of the Army permit with any deviations noted below. This determination is based upon on-site observation, scheduled, and conducted by me or by a project representative under my direct supervision. I have enclosed one set of as-built engineering drawings.

Signature of Engineer

Name (*Please type*)

(FL, PR, or VI) Reg. Number

Company Name

City

State

ZIP

(Affix Seal)

Date

Telephone Number

Date Work Started: _____ Date Work Completed: _____

Identify any deviations from the approved permit drawings and/or special conditions (attach additional pages if necessary):

[illegible]

STANDARD MANATEE CONDITIONS FOR IN-WATER WORK

2011

The permittee shall comply with the following conditions intended to protect manatees from direct project effects:

- a. All personnel associated with the project shall be instructed about the presence of manatees and manatee speed zones, and the need to avoid collisions with and injury to manatees. The permittee shall advise all construction personnel that there are civil and criminal penalties for harming, harassing, or killing manatees which are protected under the Marine Mammal Protection Act, the Endangered Species Act, and the Florida Manatee Sanctuary Act.
- b. All vessels associated with the construction project shall operate at "Idle Speed/No Wake" at all times while in the immediate area and while in water where the draft of the vessel provides less than a four-foot clearance from the bottom. All vessels will follow routes of deep water whenever possible.
- c. Siltation or turbidity barriers shall be made of material in which manatees cannot become entangled, shall be properly secured, and shall be regularly monitored to avoid manatee entanglement or entrapment. Barriers must not impede manatee movement.
- d. All on-site project personnel are responsible for observing water-related activities for the presence of manatee(s). All in-water operations, including vessels, must be shutdown if a manatee(s) comes within 50 feet of the operation. Activities will not resume until the manatee(s) has moved beyond the 50-foot radius of the project operation, or until 30 minutes elapses if the manatee(s) has not reappeared within 50 feet of the operation. Animals must not be herded away or harassed into leaving.
- e. Any collision with or injury to a manatee shall be reported immediately to the Florida Fish and Wildlife Conservation Commission (FWC) Hotline at 1-888-404-3922. Collision and/or injury should also be reported to the U.S. Fish and Wildlife Service in Jacksonville (1-904-731-3336) for north Florida or Vero Beach (1-772-562-3909) for south Florida, and to FWC at ImperiledSpecies@myFWC.com
- f. Temporary signs concerning manatees shall be posted prior to and during all in-water project activities. All signs are to be removed by the permittee upon completion of the project. Temporary signs that have already been approved for this use by the FWC must be used. One sign which reads *Caution: Boaters* must be posted. A second sign measuring at least 8 ½" by 11" explaining the requirements for "Idle Speed/No Wake" and the shut down of in-water operations must be posted in a location prominently visible to all personnel engaged in water-related activities. These signs can be viewed at MyFWC.com/manatee. Questions concerning these signs can be sent to the email address listed above.

CAUTION: MANATEE HABITAT


All project vessels

IDLE SPEED / NO WAKE

When a manatee is within 50 feet of work
all in-water activities must

SHUT DOWN

Report any collision with or injury to a manatee:



Wildlife Alert:

1-888-404-FWCC(3922)

cell *FWC or #FWC

STANDARD PROTECTION MEASURES FOR THE EASTERN INDIGO SNAKE U.S. Fish and Wildlife Service

March 23, 2021

The eastern indigo snake protection/education plan (Plan) below has been developed by the U.S. Fish and Wildlife Service (USFWS) in Florida and Georgia for use by applicants and their construction personnel. At least **30 days prior** to any clearing/land alteration activities, the applicant shall notify the appropriate USFWS Field Office via e-mail that the Plan will be implemented as described below (North Florida Field Office: jaxregs@fws.gov; South Florida Field Office: verobeach@fws.gov; Panama City Field Office: panamacity@fws.gov; Georgia Field Office: gaes_assistance@fws.gov). As long as the signatory of the e-mail certifies compliance with the below Plan (including use of the attached poster and brochure), no further written confirmation or approval from the USFWS is needed and the applicant may move forward with the project.

If the applicant decides to use an eastern indigo snake protection/education plan other than the approved Plan below, written confirmation or approval from the USFWS that the plan is adequate must be obtained. At least 30 days prior to any clearing/land alteration activities, the applicant shall submit their unique plan for review and approval. The USFWS will respond via e-mail, typically within 30 days of receiving the plan, either concurring that the plan is adequate or requesting additional information. A concurrence e-mail from the appropriate USFWS Field Office will fulfill approval requirements.

The Plan materials should consist of: 1) a combination of posters and pamphlets (see **Poster Information** section below); and 2) verbal educational instructions to construction personnel by supervisory or management personnel before any clearing/land alteration activities are initiated (see **Pre-Construction Activities** and **During Construction Activities** sections below).

POSTER INFORMATION

Posters with the following information shall be placed at strategic locations on the construction site and along any proposed access roads (a final poster for Plan compliance, to be printed on 11 x 17in or larger paper and laminated, is attached):

DESCRIPTION: The eastern indigo snake is one of the largest non-venomous snakes in North America, with individuals often reaching up to 8 feet in length. They derive their name from the glossy, blue-black color of their scales above and uniformly slate blue below. Frequently, they have orange to coral reddish coloration in the throat area, yet some specimens have been reported to only have cream coloration on the throat.

These snakes are not typically aggressive and will attempt to crawl away when disturbed. Though indigo snakes rarely bite, they should NOT be handled.

SIMILAR SNAKES: The black racer is the only other solid black snake resembling the eastern indigo snake. However, black racers have a white or cream chin, thinner bodies, and WILL BITE if handled.

LIFE HISTORY: The eastern indigo snake occurs in a wide variety of terrestrial habitat types throughout Florida and Georgia. Although they have a preference for uplands, they also utilize some wetlands and agricultural areas and often move seasonally between upland and lowland habitats, particularly in the northern portions of its range (North Florida and Georgia). Eastern indigo snakes will often seek shelter inside gopher tortoise burrows and other below- and above-ground refugia, such as other animal burrows, stumps, roots, and debris piles. Reliance on xeric sandhill habitats throughout the northern portion of the range in northern Florida and Georgia is due to the dependence on gopher tortoise burrows for shelter during winter. Breeding occurs during October through February. Females may lay from 4 - 12 white eggs as early as April through June, with young hatching in late July through October.

PROTECTION UNDER FEDERAL AND STATE LAW: The eastern indigo snake is classified as a Threatened species by both the USFWS and the Florida Fish and Wildlife Conservation Commission. Taking of eastern indigo snakes is prohibited by the Endangered Species Act without a permit is defined by the USFWS as an attempt to kill, harm, harass, pursue, hunt, shoot, wound, trap, capture, collect, or engage in any such conduct. Penalties include a maximum fine of \$25,000 for civil violations and up to \$50,000 and/or imprisonment for criminal offenses, if convicted.

Only individuals currently authorized through an issued Incidental Take Statement in association with a USFWS Biological Opinion, or by a Section 10(a)(1)(A) permit issued by the USFWS, to handle an eastern indigo snake are allowed to do so.

IF YOU SEE A LIVE EASTERN INDIGO SNAKE ON THE SITE:

- Cease clearing activities and allow the live eastern indigo snake sufficient time to move away from the site without interference;
- Personnel must NOT attempt to touch or handle snake due to protected status.
- Take photographs of the snake, if possible, for identification and documentation purposes. ^
- Immediately notify supervisor or the applicants designated agent, **and** the appropriate USFWS office, with the location information and condition of the snake.
- If the snake is located in a vicinity where continuation of the clearing or construction activities will cause harm to the snake, the activities must halt until such time that a representative of the USFWS returns the call (within one day) with further guidance as to when activities may resume.

IF YOU SEE A DEAD EASTERN INDIGO SNAKE ON THE SITE:

- Cease clearing activities and immediately notify supervisor or the applicants designated agent, **and** the appropriate USFWS office, with the location information and condition of the snake.
- Take photographs of the snake, if possible, for identification and documentation purposes.
- Thoroughly soak the dead snake in water and then freeze the specimen. The appropriate wildlife agency will retrieve the dead snake.

Telephone numbers of USFWS Florida Field Offices to be contacted if a live or dead eastern indigo snake is encountered:

North Florida Field Office: (904) 731-3336

Panama City Field Office: (850) 769-0552

South Florida Field Office: (772) 562-3909

Georgia Field Office: (706) 613-9493

PRE-CONSTRUCTION ACTIVITIES

1. The applicant or designated agent will post educational posters in the construction office and throughout the construction site, including any access roads. The posters must be clearly visible to all construction staff. A sample poster is attached.
2. Prior to the onset of construction activities, the applicant/designated agent will conduct a meeting with all construction staff (annually for multi-year projects) to discuss identification of the snake, its protected status, what to do if a snake is observed within the project area, and applicable penalties that may be imposed if state and/or federal regulations are violated. An educational brochure including color photographs of the snake will be given to each staff member in attendance and additional copies will be provided to the construction superintendent to make available in the onsite construction office (a final brochure for Plan compliance, to be printed double-sided on 8.5 x 11in paper and then properly folded, is attached). Photos of eastern indigo snakes may be accessed on USFWS and/or FWC or GADNR websites.
3. Construction staff will be informed that in the event that an eastern indigo snake (live or dead) is observed on the project site during construction activities, all such activities are to cease until the established procedures are implemented according to the Plan, which includes notification of the appropriate USFWS Field Office. The contact information for the USFWS is provided on the referenced posters and brochures.

DURING CONSTRUCTION ACTIVITIES

1. During initial site clearing activities, an onsite observer may be utilized to determine whether habitat conditions suggest a reasonable probability of an eastern indigo snake sighting (example: discovery of snake sheds, tracks, lots of refugia and cavities present in the area of clearing activities, and presence of gopher tortoises and burrows).

2. If an eastern indigo snake is discovered during gopher tortoise relocation activities (i.e. burrow excavation), the USFWS shall be contacted within one business day to obtain further guidance which may result in further project consultation.

3. Periodically during construction activities, the applicants designated agent should visit the project area to observe the condition of the posters and Plan materials, and replace them as needed. Construction personnel should be reminded of the instructions (above) as to what is expected if any eastern indigo snakes are seen.

POST CONSTRUCTION ACTIVITIES

Whether or not eastern indigo snakes are observed during construction activities, a monitoring report should be submitted to the appropriate USFWS Field Office within 60 days of project completion. The report can be sent electronically to the appropriate USFWS e-mail address listed on page one of this Plan.



ATTENTION

Federally-Threatened Eastern Indigo Snakes may be present on this site!

Killing, harming, or harassing eastern indigo snakes is strictly prohibited and punishable under State and Federal Law.

If you see a LIVE eastern indigo snake on the site:

- Do NOT attempt to touch or handle the snake. Stop land disturbing activities and allow the snake time to move away from the site without interference.
- Take photographs of the snake, if possible, for identification and documentation purposes.
- Immediately notify supervisor/applicant, and a U.S. Fish and Wildlife Service (USFWS) Ecological Services Field Office, with the location information and condition of the snake.
- If the snake is located near clearing or construction activities that will cause harm to the snake, the activities must pause until a representative of the USFWS returns the call (within one day) with further guidance.

If you see a DEAD eastern indigo snake on the site:

- Stop land disturbing activities and immediately notify supervisor/applicant, and a USFWS Ecological Services Field Office, with the location information and condition of the snake.
- Take photographs of the snake, if possible, for identification and documentation purposes.
- Thoroughly soak the dead snake in water and then freeze the specimen. The appropriate wildlife agency will retrieve the dead snake.

DESCRIPTION. The eastern indigo snake is one of the largest non-venomous snakes in North America, reaching up to 8 ft long. Named for the glossy, blue-black scales above and slate blue below, they often have orange to reddish color (cream color in some cases) in the throat area. They are not typically aggressive and will try to crawl away when disturbed.

SIMILAR SPECIES. The black racer resembles the eastern indigo snake. However, black racers have a white or cream chin, thinner bodies, and WILL BITE if handled.

LIFE HISTORY. Eastern indigo snakes live in a variety of terrestrial habitat types. Although they prefer uplands, they also use wetlands and agricultural areas. They will shelter inside gopher tortoise burrows, other animal burrows, stumps, roots, and debris piles. Females may lay from 4 to 12 white eggs as early as April through June, with young hatching in late July through October.

PROTECTED STATUS. The eastern indigo snake is protected by the USFWS, Florida Fish and Wildlife Conservation Commission, and Georgia Department of Natural Resources. Any attempt to kill, harm, harass, pursue, hunt, shoot, wound, trap, capture, collect, or engage eastern indigo snakes is prohibited by the U.S. Endangered Species Act. Penalties include a maximum fine of \$25,000 for civil violations and up to \$50,000 and/or imprisonment for criminal offenses. Only authorized individuals with a permit (i.e., Recovery [10a1A] or HCP ITP [10a1B]), or an Incidental Take Statement associated with a USFWS Biological Opinion may handle an eastern indigo snake.

Please contact your nearest USFWS Ecological Services Field Office if a live or dead eastern indigo snake is encountered:

Jacksonville, FL, (904) 731-3336
Panama City, FL, (850) 769-0552
Vero Beach, FL, (772) 562-3909
Athens, GA, (706) 613-9493



If you see a LIVE eastern indigo snake on the site:

- Cease clearing activities and allow the eastern indigo snake sufficient time to move away from the site without interference.
- Personnel must NOT attempt to touch or handle snake due to protected status.
- Take photographs of the snake, if possible, for identification and documentation purposes.
- Immediately notify supervisor or the applicant's designated agent, and the appropriate U.S. Fish and Wildlife Service (USFWS) office, with information regarding the location and condition of the snake.
- If the snake is in a vicinity where clearing or construction activities will cause harm to the snake, the activities must be paused until a representative of the USFWS returns the call (within one day) with further guidance as to when activities may resume.

If you see a DEAD eastern indigo snake on the site:

- Cease clearing activities and immediately notify the supervisor or designated applicant/agent, and the USFWS Field Office (see below for contact information), with the location and condition of the snake.
- Take photographs of the snake, if possible, for identification and documentation purposes.
- Thoroughly soak the dead snake in water and then freeze the specimen. The appropriate wildlife agency will retrieve the dead snake.

USFWS Ecological Services Field Offices to be contacted if a live or dead eastern indigo snake is encountered:

Jacksonville Office: (904) 731-3336
Panama City Office: (850) 769-0552
Vero Beach Office: (772) 562-3909
Georgia Office: (912) 403-1873

Description. The eastern indigo snake is one of the largest non-venomous snakes in North America, with individuals often reaching up to 8 feet long. They derive their name from the glossy, blue-black color of their scales above and uniformly slate blue below. They often have orange to reddish coloration in the throat area, yet some may only have cream coloration on the throat. These snakes are not typically aggressive and will attempt to crawl away when disturbed. Though indigo snakes rarely bite, they should NOT be handled.

Similar Species. The black racer is the only other solid black snake resembling the eastern indigo snake. However, black racers have a white or cream chin, thinner bodies, and WILL BITE if handled.

Life History. The eastern indigo snake occurs in a variety of terrestrial habitats. Although they prefer uplands, they also use wetlands and agricultural areas. Eastern indigo snakes will often take shelter inside gopher tortoise burrows and other below- and above-ground refugia, such as other animal burrows, stumps, roots, and debris piles. Females may lay from 4 to 12 white eggs as early as April through June, with young hatching in late July through October.

Killing, harming, or harassing indigo snakes is strictly prohibited and punishable under State and Federal Law.

Only individuals currently authorized to handle an eastern indigo snake through an issued Incidental Take Statement in association with a USFWS Biological Opinion, or by a Section 10(a)(1)(A) permit issued by the USFWS, are allowed to do so.

Legal Status. The eastern indigo snake is classified as a Threatened species by both the USFWS and the Florida Fish and Wildlife Conservation Commission. “Taking” of eastern indigo snakes is prohibited by the Endangered Species Act without a permit. “Take” is defined by the USFWS as an attempt to kill, harm, harass, pursue, hunt, shoot, wound, trap, capture, collect, or engage in any such conduct. Penalties include a maximum fine of \$25,000 for civil violations and up to \$50,000 and/or imprisonment for criminal offenses, if convicted.



ATTENTION:

**THREATENED EASTERN
INDIGO SNAKES MAY BE
PRESENT ON THIS SITE!**



*Please read the following
information provided by the U.S.
Fish and Wildlife Service on
standard protection measures for
the eastern indigo snake.*



FLORIDA DEPARTMENT OF Environmental Protection

Northwest District
160 W. Government Street, Suite 308
Pensacola, Florida 32502-5740
NWD_EPOST@dep.state.fl.us

Ron DeSantis
Governor

Jeanette Nuñez
Lt. Governor

Shawn Hamilton
Secretary

September 21, 2021

FROM:

Charles Seely
2731 Crawfordville #223
Crawfordville, Florida 32327

TO:

Kenneth Deese
3574 Travelers Rest Road
P.O. Box 575
Newton, GA 39870
kdeese69@gmail.com

Re: File No. 0245618-005-EM/65
Transfer from File No. 0245618-004-EI/65

Dear Mr. Seely and Mr. Deese,

Enclosed is a copy of the executed transfer of permit for the referenced project. The transfer of this permit to Mr. Deese is hereby approved and effective as of the date of this letter.

The Department has evaluated your request to extend the expiration date for this permit. We may extend your permit for a maximum period of five years from the date of receipt of all governmental authorizations for this project. Your permit is hereby extended until September 6, 2026. Should you be unable to complete your project by that date, you should contact the Department.

This notice of transfer and time extension does not alter the original, Specific or General Conditions, or monitoring requirements of the permit.

Please attach a copy of this letter and the enclosed transfer of permit to your permit and make them available on site during construction. When referring to this project, please use the permit number indicated.

NOTICE OF RIGHTS

This action is final and effective on the date filed with the Clerk of the Department unless a petition for an administrative hearing is timely filed under Sections 120.569 and 120.57, F.S., before the deadline for filing a petition. On the filing of a timely and sufficient petition, this action will not be final and effective until a subsequent order of the Department. Because the administrative hearing process is designed to formulate final agency action, the subsequent order may modify or take a different position than this action.

Petition for Administrative Hearing

A person whose substantial interests are affected by the Department's action may petition for an administrative proceeding (hearing) under Sections 120.569 and 120.57, F.S. Pursuant to Rules 28-106.201 and 28-106.301, F.A.C., a petition for an administrative hearing must contain the following information:

- (a) The name and address of each agency affected and each agency's file or identification number, if known;
- (b) The name, address, any e-mail address, any facsimile number, and telephone number of the petitioner, if the petitioner is not represented by an attorney or a qualified representative; the name, address, and telephone number of the petitioner's representative, if any, which shall be the address for service purposes during the course of the proceeding; and an explanation of how the petitioner's substantial interests will be affected by the agency determination;
- (c) A statement of when and how the petitioner received notice of the agency decision;
- (d) A statement of all disputed issues of material fact. If there are none, the petition must so indicate;
- (e) A concise statement of the ultimate facts alleged, including the specific facts that the petitioner contends warrant reversal or modification of the agency's proposed action;
- (f) A statement of the specific rules or statutes that the petitioner contends require reversal or modification of the agency's proposed action, including an explanation of how the alleged facts relate to the specific rules or statutes; and
- (g) A statement of the relief sought by the petitioner, stating precisely the action that the petitioner wishes the agency to take with respect to the agency's proposed action.

The petition must be filed (received by the Clerk) in the Office of General Counsel of the Department at 3900 Commonwealth Boulevard, Mail Station 35, Tallahassee, Florida 32399-3000, or via electronic correspondence at Agency_Clerk@dep.state.fl.us. Also, a copy of the petition shall be mailed to the applicant at the address indicated above at the time of filing.

Time Period for Filing a Petition

In accordance with Rule 62-110.106(3), F.A.C., petitions for an administrative hearing by the applicant and persons entitled to written notice under Section 120.60(3), F.S., must be filed within 21 days of receipt of this written notice. Petitions filed by any persons other than the applicant, and other than those entitled to written notice under Section 120.60(3), F.S., must be filed within 21 days of publication of the notice or within 21 days of receipt of the written notice, whichever occurs first. You cannot justifiably rely on the finality of this decision unless notice of this decision and the right of substantially affected persons to challenge this decision has been duly published or otherwise provided to all persons substantially affected by the decision. While

you are not required to publish notice of this action, you may elect to do so pursuant Rule 62-110.106(10)(a).

The failure to file a petition within the appropriate time period shall constitute a waiver of that person's right to request an administrative determination (hearing) under Sections 120.569 and 120.57, F.S., or to intervene in this proceeding and participate as a party to it. Any subsequent intervention (in a proceeding initiated by another party) will be only at the discretion of the presiding officer upon the filing of a motion in compliance with Rule 28-106.205, F.A.C. If you do not publish notice of this action, this waiver may not apply to persons who have not received a clear point of entry.

Extension of Time

Under Rule 62-110.106(4), F.A.C., a person whose substantial interests are affected by the Department's action may also request an extension of time to file a petition for an administrative hearing. The Department may, for good cause shown, grant the request for an extension of time. Requests for extension of time must be filed with the Office of General Counsel of the Department at 3900 Commonwealth Boulevard, Mail Station 35, Tallahassee, Florida 32399-3000, or via electronic correspondence at Agency_Clerk@FloridaDEP.gov, before the deadline for filing a petition for an administrative hearing. A timely request for extension of time shall toll the running of the time period for filing a petition until the request is acted upon.

Mediation

Mediation is not available in this proceeding.

FLAWAC Review

The applicant, or any party within the meaning of Section 373.114(1)(a) or 373.4275, F.S., may also seek appellate review of this order before the Land and Water Adjudicatory Commission under Section 373.114(1) or 373.4275, F.S. Requests for review before the Land and Water Adjudicatory Commission must be filed with the Secretary of the Commission and served on the Department within 20 days from the date when this order is filed with the Clerk of the Department.

Judicial Review

Once this decision becomes final, any party to this action has the right to seek judicial review pursuant to Section 120.68, F.S. by filing a Notice of Appeal pursuant to Florida Rules of Appellate Procedure 9.110 and 9.190 with the Clerk of the Department in the Office of General Counsel (Station #35, 3900 Commonwealth Boulevard, Tallahassee, Florida 32399-3000) and by filing a copy of the Notice of Appeal accompanied by the applicable filing fees with the appropriate district court of appeal. The notice must be filed within 30 days from the date this action is filed with the Clerk of the Department.

If you have any questions regarding this matter, please contact Allison Pritchard at the letterhead address, at 850-595-0564, or at Allison.Pritchard@FloridaDEP.gov

EXECUTION AND CLERKING

Executed in Orlando, Florida.

STATE OF FLORIDA DEPARTMENT OF ENVIRONMENTAL PROTECTION



Kimberly R. Allen
Permitting Program Administrator

Attachments:

1. Permit File No. 0245618-004-EI/65, 20 pages
2. Permit Transfer Request, 4 pages

CERTIFICATE OF SERVICE


The undersigned duly designated deputy clerk hereby certifies that this document and all attachments were sent on the filing date below to the following listed persons:

CC:

Blake Chapman, DEP, Blake.A.Chapman@FloridaDEP.gov
Sue Maxwell, U.S. Army Corps of Engineers, Susanna.R.Maxwell@usace.army.mil
Kevin Easton, Florida Environmental and Land Services, keaston@felsi.org
Aaron Sarchet, Project Manager/ Environmental Specialist, ASarchet@felsi.org
Anna Wickman, Authorized Agent, awickman@felsi.org
Department of Economic Opportunity, Ray.Eubanks@deo.myflorida.com,
DCPPpermits@deo.myflorida.com
Department of Agriculture and Consumer Services, kal.knickerbocker@freshfromflorida.com,
jillian.fleiger@freshfromflorida.com
Wakulla County, mail@cityofstmarks.com, Rwilde@mywakulla.com,
ashley.schilling@sopchoppy.org, William.gibson@flhealth.gov, dedwards@mywakulla.com

FILING AND ACKNOWLEDGMENT

FILED, on this date, pursuant to Section 120.52, F.S., with the designated Department Clerk, receipt of which is hereby acknowledged.



Clerk

September 21, 2021

Date



Florida Department of Environmental Protection

160 W. Government Street, Suite 308
Pensacola, Florida 32502-5740

Rick Scott
Governor

Carlos Lopez-Cantera
Lt. Governor

Jonathan P. Steverson
Secretary

Permittee/Authorized Entity:

Charles Seeley
2731 Crawfordville #223
Crawfordville, Florida 32327

Seeley – Canal Dock, Dredge, and Stabilization

Authorized Agent:

Florida Environmental and Land Services, Inc.
Anna Wickman
221-4 Delta Court
Tallahassee, Florida 32303
awickman@felsi.org

Environmental Resource Permit

State-owned Submerged Lands Authorization – Not Applicable

**U.S. Army Corps of Engineers Authorization – Separate Corps Authorization
Required**

Wakulla County
Permit No.: 65-0245618-004-EI

Permit Issuance Date: September 6, 2016
Permit Construction Phase Expiration Date: September 5, 2021

Environmental Resource Permit

Permittee: Charles Seeley
Permit No: 65-0245618-004-EI

PROJECT LOCATION

The activities authorized by this permit are located at the intersection of Canal Street and Southside Drive in Crawfordville, Florida, 32327, in Section 121, Township 5 South, Range 1 West in Wakulla County, at Latitude 30°4'33.46" N / Longitude 84°18'1.42" W.

The parcel ID# for the upland multi-family development is 00-00-121-000-11962-003 and the canal bottom land is untaxed property described in a Warranty Deed recorded in the Official Records of Wakulla County, Book 649, Pages 110-113.

PROJECT DESCRIPTION

The permittee is authorized to construct a 1,556 square-foot, 23-slip multi-family dock consisting of a 6-foot by 4-foot stationary walkway, a 258-foot by 4-foot floating dock, twelve (12) 3-foot by 12-foot finger-piers, and one (1) 20-foot by 4-foot finger-pier. The permittee is also authorized to place 117 cubic-yards of rip rap along 76-foot of shoreline around three existing culverts, which will also undergo maintenance to remove accumulated sediment. The permittee is also authorized to maintenance dredge 4,240 cubic-yards of material over 22,750 square-foot of area to a depth of 5-foot below Mean High Water Line (MHWL), after which the spoil material will be placed in a self-contained upland storage location until dry, after which it will be transported to a Class I landfill that is authorized to accept hazardous waste. The permittee is also authorized to place 440 linear-foot of seawall along the east and west portions of the canal, along with approximately 40 cubic-yards of backfill material. The above described activities will take place in a man-made canal adjacent to Oyster Bay / Gulf of Mexico, Class II Waters of the State, Conditionally Restricted Shellfish Harvesting Area. Authorized activities are depicted on the attached exhibits.

AUTHORIZATIONS

Seeley – Canal Dock, Dredge, and Stabilization

Environmental Resource Permit

The Department has determined that the activity qualifies for an Environmental Resource Permit. Therefore, the Environmental Resource Permit is hereby granted, pursuant to Part IV of Chapter 373, Florida Statutes (F.S.), and Chapter 62-330, Florida Administrative Code (F.A.C.).

Sovereignty Submerged Lands Authorization

As staff to the Board of Trustees of the Internal Improvement Trust Fund (Board of Trustees), the Department has determined the activity is not on submerged lands owned by the State of Florida. Therefore, your project is not subject to the requirements of Chapter 253, F.S., or Rule 18-21, F.A.C.

Federal Authorization

Your proposed activity as outlined on your application and attached drawings **does not qualify** for Federal authorization pursuant to the State Programmatic General Permit and a **SEPARATE permit** or authorization **may be required** from the Corps. A copy of your permit application has been forwarded to the Corps for their review. The Corps will issue their authorization directly to you or contact you if additional information is needed. If you have not heard from the Corps within 30 days from the date your application was received at the local FDEP Office, contact the Corps at the Panama City Regulatory Office at 850-763-0717, for status and further information. **Failure to obtain Corps authorization prior to construction could subject you to federal enforcement action by that agency.**

Authority for review - an agreement with the USACOE entitled "Coordination Agreement Between the U. S. Army Corps of Engineers (Jacksonville District) and the Florida Department of Environmental Protection, or Duly Authorized Designee, State Programmatic General Permit", Section 10 of the Rivers and Harbor Act of 1899, and Section 404 of the Clean Water Act.

Coastal Zone Management

Issuance of this authorization also constitutes a finding of consistency with Florida's Coastal Zone Management Program, as required by Section 307 of the Coastal Zone Management Act.

Water Quality Certification

This permit also constitutes a water quality certification under Section 401 of the Clean Water Act, 33 U.S.C. 1341.

Other Authorizations

You are advised that authorizations or permits for this activity may be required by other federal, state, regional, or local entities including but not limited to local governments or municipalities. This permit does not relieve you from the requirements to obtain all other required permits or authorizations.

The activity described may be conducted only in accordance with the terms, conditions and attachments contained in this document. Issuance and granting of the permit and authorizations herein do not infer, nor guarantee, nor imply that future permits, authorizations, or modifications will be granted by the Department.

PERMIT

The activities described must be conducted in accordance with:

- **The Specific Conditions**
- **The General Conditions**
- **The limits, conditions and locations of work shown in the attached drawings**
- **The term limits of this authorization**

You are advised to read and understand these conditions and drawings prior to beginning the authorized activities, and to ensure the work is conducted in conformance with all the terms, conditions, and drawings herein. If you are using a contractor, the contractor also should read and understand these conditions and drawings prior to beginning any activity. Failure to comply with

Permittee: Charles Seeley

Permit No: 65-0245618-004-EI

Page 3 of 13

these conditions, including any mitigation requirements, shall be grounds for the Department to revoke the permit and authorization and to take appropriate enforcement action. Operation of the facility is not authorized except when determined to be in conformance with all applicable rules and this permit.

SPECIFIC CONDITIONS - PRIOR TO ANY CONSTRUCTION

1. If the approved permit drawings conflict with the specific conditions, then the specific conditions shall prevail.
2. The structure/work authorized by this permit shall not be placed/conducted on any property, other than that owned by the permittee, without the prior written approval of that property owner.
3. This permit does not authorize the construction of any additional structures not illustrated on the permit drawings.
4. After selection of the contractor to perform the authorized activities and prior to the initiation of any work authorized by this permit, the permittee (or authorized agent) and the contractor shall attend a pre-construction conference with a representative of the Department. It shall be the responsibility of the permittee to contact this project's compliance coordinator, Michael Mathews, by email at Michael.Mathews@dep.state.fl.us, or by phone (850) 595-0042, to schedule the pre-construction conference.
5. The permittee shall ensure that the permit conditions are explained to all construction personnel working on the project and for providing each contractor and subcontractor with a copy of this permit before the authorized work begins.
6. Prior to the initiation of any work authorized by this permit, floating turbidity screens with weighted skirts that extend to within 1 ft. of the bottom shall be placed around the project area. The screens shall be maintained and shall remain in place for the duration of the project construction to ensure that turbidity levels outside the construction area do not exceed 29 NTU's above background levels. The permittee shall be responsible for ensuring that turbidity control devices are inspected daily and maintained in good working order so that there are no violations of state water quality standards outside of the turbidity screens.
7. Best management practices for erosion control shall be implemented and maintained at all times during construction to prevent siltation and turbid discharges in excess of State water quality standards pursuant to Rule 62-302, F.A.C. Methods shall include, but are not limited to the use of staked hay bales, staked filter cloth, sodding, seeding, and mulching; staged construction; and the installation of turbidity screens around the immediate project site.

SPECIFIC CONDITIONS – CONSTRUCTION ACTIVITIES

8. All areas to be dredged shall be in accordance with the attached permit drawings and shall not exceed the areas and depths indicated on those drawings. Any impact that occurs outside of the authorized area is prohibited.

9. Dredging shall be limited to day light; no dredging (or dewatering) activities are authorized to be conducted at night.
10. All cleared vegetation, excess lumber, scrap wood, trash, garbage and any other type of debris shall be removed from wetlands/waters of the state within 14 days of completion of the work authorized in this permit.
11. There shall be no storage or stockpiling of tools or materials (i.e., lumber, pilings, equipment) within wetlands, along the shoreline within the littoral zone, or elsewhere within waters of the state unless specifically approved in the permit.
12. All excavated material shall be placed in a self-contained, upland disposal site. The slopes of the spoil material disposal cell shall be stabilized utilizing staked hay bales and entrenched silt fence and/or geotextile fabric in order to prevent the escape of spoil material and associated effluent into surface waters. At no time will spoil material or water discharge into waters of the State.
13. The permittee shall inspect the Dredge Disposal Management Area (DDMA) and conduct maintenance to ensure the structures integrity throughout operation. Maintenance and routine inspections shall be conducted in accordance with the Minimum Operation and Maintenance Requirements. The permittee must maintain a record of each inspection and make such record available upon request of the Department. Each record shall include the date of inspection, the name and contact information of the inspector, whether the facility was functioning as designed and permitted, and whether any maintenance activities resulted from the inspection.
14. Within 30 days of the end of work authorized by this permit, or at the earliest point that the material has dried sufficiently for transport, the dredged material shall be transported to a Class I Landfill facility that is able to accept hazardous waste. After all dredged material is transported and disposed of properly, the permittee shall provide receipts or other proof to the Department that the material was received by the facility.
15. Best management practices for erosion control shall be implemented and maintained at all times during construction to prevent siltation and turbid discharges in excess of State water quality standards pursuant to Rule 62-302, F.A.C. Methods shall include, but are not limited to the use of staked hay bales, staked filter cloth, sodding, seeding, and mulching; staged construction; and the installation of turbidity screens around the immediate project site.
16. The permittee shall be responsible for ensuring that erosion control devices/procedures are inspected and maintained daily during all phases of construction authorized by this permit until all areas that were disturbed during construction are sufficiently stabilized to prevent erosion, siltation, and turbid discharges.

The following measures shall be taken immediately by the permittee whenever turbidity levels within waters of the State surrounding the project site, exceed 29 NTUs above background:

- a. Immediately cease all work contributing to the water quality violation.

- b. Stabilize all exposed soils contributing to the violation. Modify the work procedures that were responsible for the violation and install more turbidity containment devices and repair any non-functioning turbidity containment devices.
 - c. Notify the FDEP Northwest District Panama City Branch Office at (850) 872-4375, or at the address in Special Condition 22 within 24 hours of the time the violation is first detected.
17. All wetland areas or water bodies which are adjacent to the specific limits of construction authorized by this permit, and all state owned waterbodies in the vicinity, shall be protected from erosion, sedimentation, siltation, scouring, excess turbidity or dewatering.
18. The seawall shall be fully constructed prior to the placement of any backfill material. Any fill material used behind the seawall shall be clean fill and free of vegetative matter, trash, garbage, toxic or hazardous waste or any other unsuitable materials.
19. Riprap shall consist of unconsolidated boulders, rocks, or clean concrete rubble with no exposed reinforcing rods or similar protrusions. The riprap shall be free of sediment, debris and any toxic or otherwise deleterious substance.
20. The slope of the riprap shall be no steeper than 2:1 horizontal to vertical and shall extend no more than 10-foot waterward of the mean high water.
21. Dredging within waters of the State for the purpose of providing fill material is specifically prohibited.
22. There shall be no boat repair facilities on any structure that is over the water. No overboard discharges of trash, human or animal waste, or fuel shall occur at the pier.
23. Construction equipment shall not be repaired or refueled in wetlands or other surface waters.
24. All watercraft associated with the construction and operation of the permitted structure shall only operate within waters of sufficient depth so as to preclude bottom scouring/prop dredging. The draft of all vessels utilizing the dock must allow for at least one foot of clearance above the bottom of the waterbody mean low tide.
25. There shall be no enclosed sides constructed on the dock.
26. For emergencies involving a serious threat to the public health, safety, welfare, or environment, the emergency telephone contact number is **800-320-0519** (State Warning Point). The Department telephone number for reporting nonthreatening problems or system malfunctions is (850) 595-0663, day or night.

27. The construction phase expires at 11:59 p.m. on the date indicated on the cover page of this permit, unless an application for extension is received and approved pursuant to Rule 62-346.120, F.A.C.
28. The mailing address for submittal of forms for the “Construction Commencement Notice” or other correspondence is FDEP, SLERP, 470 Harrison Avenue, Panama City, Florida 32401.

SPECIFIC CONDITIONS – OPERATION AND MAINTENANCE ACTIVITIES

29. All structures authorized by this permit shall remain in operable condition and shall not be allowed to deteriorate or otherwise contribute to a water quality violation for the life of the facility.
30. Overboard discharges of trash, human or animal waste, or fuel shall not occur at the dock. The permittee shall provide, maintain, and service sufficient marked trash receptacles in the uplands to accommodate the public usage of the facility.
31. The dock structure approved under this permit shall only serve as a private, multi-family dock for the future development of 23 residential units on the permittee’s upland property.

GENERAL CONDITIONS FOR INDIVIDUAL PERMITS

The following general conditions are binding on all individual permits issued under chapter 62-330, F.A.C., except where the conditions are not applicable to the authorized activity, or where the conditions must be modified to accommodate project-specific conditions.

1. All activities shall be implemented following the plans, specifications and performance criteria approved by this permit. Any deviations must be authorized in a permit modification in accordance with Rule 62-330.315, F.A.C. Any deviations that are not so authorized may subject the permittee to enforcement action and revocation of the permit under Chapter 373, F.S.
2. A complete copy of this permit shall be kept at the work site of the permitted activity during the construction phase, and shall be available for review at the work site upon request by the Agency staff. The permittee shall require the contractor to review the complete permit prior to beginning construction.
3. Activities shall be conducted in a manner that does not cause or contribute to violations of state water quality standards. Performance-based erosion and sediment control best management practices shall be installed immediately prior to, and be maintained during and after construction as needed, to prevent adverse impacts to the water resources and adjacent lands. Such practices shall be in accordance with the *State of Florida Erosion and Sediment Control Designer and Reviewer Manual (Florida Department of Environmental Protection and Florida Department of Transportation June 2007)*, and the *Florida Stormwater Erosion and Sedimentation Control Inspector’s Manual (Florida Department of Environmental Protection, Nonpoint Source Management Section, Tallahassee, Florida, July 2008)*, which are both incorporated by reference in subparagraph 62-330.050(9)(b)5., F.A.C., unless a project-specific erosion and sediment control plan is approved or other water quality control measures are required as part of the permit.

4. At least 48 hours prior to beginning the authorized activities, the permittee shall submit to the Agency a fully executed Form 62-330.350(1), "Construction Commencement Notice," [October 1, 2013], which is incorporated by reference in paragraph 62-330.350(1)(d), F.A.C., indicating the expected start and completion dates. A copy of this form may be obtained from the Agency, as described in subsection 62-330.010(5), F.A.C. If available, an Agency website that fulfills this notification requirement may be used in lieu of the form.
5. Unless the permit is transferred under Rule 62-330.340, F.A.C., or transferred to an operating entity under Rule 62-330.310, F.A.C., the permittee is liable to comply with the plans, terms and conditions of the permit for the life of the project or activity.
6. Within 30 days after completing construction of the entire project, or any independent portion of the project, the permittee shall provide the following to the Agency, as applicable:
 - a. For an individual, private single-family residential dwelling unit, duplex, triplex, or quadruplex – "Construction Completion and Inspection Certification for Activities Associated With a Private Single-Family Dwelling Unit" [Form 62-330.310(3)]; or
 - b. For all other activities – "As-Built Certification and Request for Conversion to Operational Phase" [Form 62-330.310(1)].
 - c. If available, an Agency website that fulfills this certification requirement may be used in lieu of the form.
7. If the final operation and maintenance entity is a third party:
 - a. Prior to sales of any lot or unit served by the activity and within one year of permit issuance, or within 30 days of as- built certification, whichever comes first, the permittee shall submit, as applicable, a copy of the operation and maintenance documents (see sections 12.3 thru 12.3.3 of Volume I) as filed with the Department of State, Division of Corporations and a copy of any easement, plat, or deed restriction needed to operate or maintain the project, as recorded with the Clerk of the Court in the County in which the activity is located.
 - b. Within 30 days of submittal of the as- built certification, the permittee shall submit "Request for Transfer of Environmental Resource Permit to the Perpetual Operation Entity" [Form 62-330.310(2)] to transfer the permit to the operation and maintenance entity, along with the documentation requested in the form. If available, an Agency website that fulfills this transfer requirement may be used in lieu of the form.
8. The permittee shall notify the Agency in writing of changes required by any other regulatory agency that require changes to the permitted activity, and any required modification of this permit must be obtained prior to implementing the changes.
9. This permit does not:
 - a. Convey to the permittee any property rights or privileges, or any other rights or privileges other than those specified herein or in Chapter 62-330, F.A.C.;
 - b. Convey to the permittee or create in the permittee any interest in real property;
 - c. Relieve the permittee from the need to obtain and comply with any other required federal, state, and local authorization, law, rule, or ordinance; or

- d. Authorize any entrance upon or work on property that is not owned, held in easement, or controlled by the permittee.
10. Prior to conducting any activities on state-owned submerged lands or other lands of the state, title to which is vested in the Board of Trustees of the Internal Improvement Trust Fund, the permittee must receive all necessary approvals and authorizations under Chapters 253 and 258, F.S. Written authorization that requires formal execution by the Board of Trustees of the Internal Improvement Trust Fund shall not be considered received until it has been fully executed.
11. The permittee shall hold and save the Agency harmless from any and all damages, claims, or liabilities that may arise by reason of the construction, alteration, operation, maintenance, removal, abandonment or use of any project authorized by the permit.
12. The permittee shall notify the Agency in writing:
 - a. Immediately if any previously submitted information is discovered to be inaccurate; and
 - b. Within 30 days of any conveyance or division of ownership or control of the property or the system, other than conveyance via a long-term lease, and the new owner shall request transfer of the permit in accordance with Rule 62-330.340, F.A.C. This does not apply to the sale of lots or units in residential or commercial subdivisions or condominiums where the stormwater management system has been completed and converted to the operation phase.
13. Upon reasonable notice to the permittee, Agency staff with proper identification shall have permission to enter, inspect, sample and test the project or activities to ensure conformity with the plans and specifications authorized in the permit.
14. If any prehistoric or historic artifacts, such as pottery or ceramics, stone tools or metal implements, dugout canoes, or any other physical remains that could be associated with Native American cultures, or early colonial or American settlement are encountered at any time within the project site area, work involving subsurface disturbance in the immediate vicinity of such discoveries shall cease. The permittee or other designee shall contact the Florida Department of State, Division of Historical Resources, Compliance and Review Section, at (850) 245-6333 or (800) 847-7278, as well as the appropriate permitting agency office. Such subsurface work shall not resume without verbal or written authorization from the Division of Historical Resources. If unmarked human remains are encountered, all work shall stop immediately and notification shall be provided in accordance with Section 872.05, F.S.
15. Any delineation of the extent of a wetland or other surface water submitted as part of the permit application, including plans or other supporting documentation, shall not be considered binding unless a specific condition of this permit or a formal determination under Rule 62-330.201, F.A.C., provides otherwise.
16. The permittee shall provide routine maintenance of all components of the stormwater management system to remove trapped sediments and debris. Removed materials shall be disposed of in a landfill or other uplands in a manner that does not require a permit under Chapter 62-330, F.A.C., or cause violations of state water quality standards.

17. This permit is issued based on the applicant's submitted information that reasonably demonstrates that adverse water resource-related impacts will not be caused by the completed permit activity. If any adverse impacts result, the Agency will require the permittee to eliminate the cause, obtain any necessary permit modification, and take any necessary corrective actions to resolve the adverse impacts.
18. A Recorded Notice of Environmental Resource Permit may be recorded in the county public records in accordance with subsection 62-330.090(7), F.A.C. Such notice is not an encumbrance upon the property.

NOTICE OF RIGHTS

This action is final and effective on the date filed with the Clerk of the Department unless a petition for an administrative hearing is timely filed under Sections 120.569 and 120.57, F.S., before the deadline for filing a petition. On the filing of a timely and sufficient petition, this action will not be final and effective until further order of the Department. Because the administrative hearing process is designed to formulate final agency action, the hearing process may result in a modification of the agency action or even denial of the application.

Petition for Administrative Hearing

A person whose substantial interests are affected by the Department's action may petition for an administrative proceeding (hearing) under Sections 120.569 and 120.57, F.S. Pursuant to Rule 28-106.201, F.A.C., a petition for an administrative hearing must contain the following information:

- (a) The name and address of each agency affected and each agency's file or identification number, if known;
- (b) The name, address, any email address, any facsimile number, and telephone number of the petitioner; the name, address, and telephone number of the petitioner's representative, if any, which shall be the address for service purposes during the course of the proceeding; and an explanation of how the petitioner's substantial interests are or will be affected by the agency determination;
- (c) A statement of when and how the petitioner received notice of the agency decision;
- (d) A statement of all disputed issues of material fact. If there are none, the petition must so indicate;
- (e) A concise statement of the ultimate facts alleged, including the specific facts that the petitioner contends warrant reversal or modification of the agency's proposed action;
- (f) A statement of the specific rules or statutes that the petitioner contends require reversal or modification of the agency's proposed action, including an explanation of how the alleged facts relate to the specific rules or statutes; and
- (g) A statement of the relief sought by the petitioner, stating precisely the action that the petitioner wishes the agency to take with respect to the agency's proposed action.

The petition must be filed (received by the Clerk) in the Office of General Counsel of the Department at 3900 Commonwealth Boulevard, Mail Station 35, Tallahassee, Florida 32399-3000. Also, a copy of the petition shall be mailed to the applicant at the address indicated above at the time of filing.

Time Period for Filing a Petition

In accordance with Rule 62-110.106(3), F.A.C., petitions for an administrative hearing by the applicant must be filed within 21 days of receipt of this written notice. Petitions filed by any persons other than the applicant, and other than those entitled to written notice under Section 120.60(3), F.S., must be filed within 21 days of publication of the notice or within 21 days of receipt of the written notice, whichever occurs first. Under Section 120.60(3), F.S., however, any person who has asked the Department for notice of agency action may file a petition within 21 days of receipt of such notice, regardless of the date of publication. The failure to file a petition within the appropriate time period shall constitute a waiver of that person's right to request an administrative determination (hearing) under Sections 120.569 and 120.57, F.S., or to intervene in this proceeding and participate as a party to it. Any subsequent intervention (in a proceeding initiated by another party) will be only at the discretion of the presiding officer upon the filing of a motion in compliance with Rule 28-106.205, F.A.C.

Extension of Time

Under Rule 62-110.106(4), F.A.C., a person whose substantial interests are affected by the Department's action may also request an extension of time to file a petition for an administrative hearing. The Department may, for good cause shown, grant the request for an extension of time. Requests for extension of time must be filed with the Office of General Counsel of the Department at 3900 Commonwealth Boulevard, Mail Station 35, Tallahassee, Florida 32399-3000, before the applicable deadline for filing a petition for an administrative hearing. A timely request for extension of time shall toll the running of the time period for filing a petition until the request is acted upon.

Mediation

Mediation is not available in this proceeding.

FLAWAC Review

The applicant, or any party within the meaning of Section 373.114(1)(a) or 373.4275, F.S., may also seek appellate review of this order before the Land and Water Adjudicatory Commission under Section 373.114(1) or 373.4275, F.S. Requests for review before the Land and Water Adjudicatory Commission must be filed with the Secretary of the Commission and served on the Department within 20 days from the date when this order is filed with the Clerk of the Department.


Judicial Review

Once this decision becomes final, any party to this action has the right to seek judicial review pursuant to Section 120.68, F.S., by filing a Notice of Appeal pursuant to Rules 9.110 and 9.190, Florida Rules of Appellate Procedure, with the Clerk of the Department in the Office of General Counsel, 3900 Commonwealth Boulevard, M.S. 35, Tallahassee, Florida 32399-3000; and by filing a copy of the Notice of Appeal accompanied by the applicable filing fees with the appropriate District Court of Appeal. The Notice of Appeal must be filed within 30 days from the date this action is filed with the Clerk of the Department.

If you have any questions regarding this matter, please contact Jared Searcy at the letterhead address, at 850-245-7625 or at Jared.Searcy@dep.state.fl.us.

Executed in Orlando, Florida.

STATE OF FLORIDA DEPARTMENT
OF ENVIRONMENTAL PROTECTION



Andrew Joslyn
Permitting Program Administrator

Attachments:

Exhibit 1, Project Drawings and Design Specs., 7 pages

Copies furnished to:

Sue Maxwell, U.S. Army Corps of Engineers, Susanna.R.Maxwell@usace.army.mil

Kevin Easton, Florida Environmental and Land Services, keaston@felsi.org

Department of Economic Opportunity, Ray.Eubanks@deo.myflorida.com

DCPPPermits@deo.myflorida.com

Department of Agriculture and Consumer Services, kal.knickerbocker@freshfromflorida.com

jillian.fleiger@freshfromflorida.com

CERTIFICATE OF SERVICE

The undersigned hereby certifies that this permit, including all copies, were mailed before the close of business on **September 6, 2015**, to the above listed persons.

FILING AND ACKNOWLEDGMENT

FILED, on this date, under 120.52(7) of the Florida Statutes, with the designated Department Clerk, receipt of which is hereby acknowledged.




Clerk

September 6, 2016

Date

<p>FLORIDA ENVIRONMENTAL AND LAND SERVICES, INC.</p> <p>221-4 Delta Court TALLAHASSEE, FLORIDA 32303</p> <p>850-385-6255 (VOICE) 850-385-6355 (FAX)</p>	<p>PROJECT</p> <p>Oyster Bay Permit Modification Permit # 65-0245618-002DF Wakulla, Florida</p>	<p>TITLE</p> <p>Plan View-Canal Dredging</p>	<table border="1"> <tr> <td data-bbox="1500 302 1521 598">DATE 4-16-08 Rev. 8-11-08</td> <td data-bbox="1521 302 1542 598">BY: RBS</td> <td data-bbox="1542 302 1563 598">CHK: PROJ:</td> <td data-bbox="1563 302 1573 598">04-0325</td> </tr> </table>	DATE 4-16-08 Rev. 8-11-08	BY: RBS	CHK: PROJ:	04-0325	<p>PAGE: 1</p> <p>OF: 4</p>
DATE 4-16-08 Rev. 8-11-08	BY: RBS	CHK: PROJ:	04-0325					



N.T.S.

AREA TO BE DREDGED
TOTAL QUANTITY =
4,240 CU. YDS. (INCLUDES
AREA ABOVE & BELOW MHW)



SELLERS CONSULTING, LLC

525 JOHN KNOX ROAD, SUITE D
TALLAHASSEE, FLORIDA 32303

PH: 850 386-7022
FAX: 850 386-7029

CIVIL ENGINEERING ENVIRONMENTAL PERMITTING LAND PLANNING
CERTIFICATE OF AUTHORIZATION NUMBER 20025

ROBERT B. SELLERS, P.E. FLA. REG. NO. 53217



Handwritten signature and date 8/30/16

Figure 5

FLORIDA ENVIRONMENTAL AND LAND SERVICES, INC. 221-4 Delta Court TALLAHASSEE, FLORIDA 32303 850-385-6255 (VOICE) 850-385-6355 (FAX)	PROJECT Oyster Bay Permit Modification Permit # 65-0245618-002DF Wakulla, Florida	TITLE Canal Dredging-Cross Section	PAGE: 2
		DATE 4-16-08 Rev. 8-11-08	CHK: RBS PROJ.: 04-0325 OF: 4



SCALE 1" = 50'



STATIONARY WALKWAY	=	24 SQ. FT.
FLOATING DOCK (INCLUDES RAMPS)	=	1,016 SQ. FT.
FINGER PIERS	=	516 SQ. FT.
TOTAL	=	1,556 SQ. FT.

SELLERS CONSULTING, LLC

525 JOHN KNOX ROAD, SUITE D
TALLAHASSEE, FLORIDA 32303

PH: 850 385-7022
FAX: 850 385-7029

CIVIL ENGINEERING ENVIRONMENTAL PERMITTING LAND PLANNING
CERTIFICATE OF AUTHORIZATION NUMBER 20055

ROBERT B. SELLERS, P.E. FLA. REG. NO. 53217

Handwritten signature and date: 8/26/16

NOTE: PROPOSED SEAWALL, FLOATING DOCK,
FINGER PIERS AND STATIONARY WALKWAY
ARE TO BE DESIGNED BY OTHERS


Figure 6

FLORIDA ENVIRONMENTAL AND LAND SERVICES, INC. 221-4 Delta Court TALLAHASSEE, FLORIDA 32303 850-385-6255 (VOICE) 850-385-6355 (FAX)	PROJECT	Oyster Bay Permit Modification Permit # 65-0245618-002DF Wakulla, Florida	TITLE	Plan View-Docks	PAGE: 3
	DATE	4-16-08 Rev. 8-11-08	CHK:	RBS	BY:
					OF: 4



5 of 7 8/30/16
65-0245618-004-ET

NOTE: DESIGN OF WALKWAY, DOCK AND
PIERS BY OTHERS.



N.T.S.

Robert B. Sellers, P.E.
8/22/08

SELLERS CONSULTING, LLC

525 JOHN KNOX ROAD, SUITE D
TALLAHASSEE, FLORIDA 32303
PH: 850 386-7022
FAX: 850 386-7029

CIVIL ENGINEERING ENVIRONMENTAL PERMITTING LAND PLANNING
CERTIFICATE OF AUTHORIZATION NUMBER 20555

ROBERT B. SELLERS, P.E. FLA. REG. NO. 53217

Figure 7

FLORIDA ENVIRONMENTAL AND LAND SERVICES, INC. 221-4 Delta Court TALLAHASSEE, FLORIDA 32303 850-385-6255 (VOICE) 850-385-6355 (FAX)	PROJECT Oyster Bay Permit Modification Permit # 65-0245618-002DF Wakulla, Florida	TITLE Dock-Cross Section	PAGE: 4
	DATE 4-16-08 Rev. 8-11-08	CHK: RBS	BY: 8-11-08





6 of 7 8/30/16
65-0245618-004-ET

11 06 12:34p

Elva Peppers


8503850355

P. 13



Southside Drive

Lot 20



DAVID H. MELVIN, INC.
Consulting Engineers

4428 LAVETTE STREET
MARIANNA, FLORIDA 32447
(850) 482-3015

2831 KERRY FOREST DRIVE, STE. 103
TALLAHASSEE, FLORIDA 32309
(850) 671-7721

3203 S. HIGHWAY 77, STE. B
LITHIA HAVEN, FLORIDA 32444
(850) 248-5111
P.O. BOX 10000

O. SEAN MARTIN, PE

[Signature]
1/11/2006



FLORIDA REG. #53839

Figure 8

FLORIDA ENVIRONMENTAL AND LAND SERVICES, INC.
285 PINEWOOD DRIVE
TALLAHASSEE, FLORIDA 32303
850-385-6255 (VOICE) 850-385-6355 (FAX)

PROJECT
Oyster Bay Canal Street Wakulla, Florida

Applicant: Charles Seely
File: 20052601 NW-SWA
Date: 27 February 2006
Page 1 of 8



DAVID H. MELVIN, INC.
Consulting Engineers
4428 LAFAYETTE STREET
TALLAHASSEE, FLORIDA 32347
(850) 482-3318

2831 NORTON FOREST PARK, STE. 100
TALLAHASSEE, FLORIDA 32309
(850) 671-7221

3503 S. MONROE ST., STE. B
TALLAHASSEE, FLORIDA 32344
(850) 248-3111

PR. 4/20/2006

O. SEAN MARTIN, PE


[Signature]
1/11/2006

FLORIDA REG. #53939

Figure 90

FLORIDA ENVIRONMENTAL AND LAND SERVICES, INC. 285 PINEWOOD DRIVE TALLAHASSEE, FLORIDA 32303 850-385-6255 (VOICE) 850-385-6355 (FAX)	PROJECT Oyster Bay Canal Street Wakulla, Florida	Applicant: Charles Seely File: 20052601 NW-SWA Date: 27 February 2006 Page 4 of 8
---	---	---

Project Plans



SCALE 1" = 50'

DREDGING IN CANAL
TOTAL QUANTITY =
3,750 CU. YDS.

DREDGING ABOVE
MEAN HIGH WATER
TOTAL QUANTITY =
490 CU. YDS.

SELLERS CONSULTING, LLC
525 JOHN KNOX ROAD, SUITE D PH: 850 386-7022
TALLAHASSEE, FLORIDA 32303 FAX: 850 386-7029
CIVIL ENGINEERING ENVIRONMENTAL PERMITTING LAND PLANNING
CERTIFICATE OF AUTHORIZATION NUMBER 20055
ROBERT B. SELLERS, P.E. FLA. REG. NO. 53217


Robert B. Sellers
8/26/16

Figure 4

FLORIDA ENVIRONMENTAL AND LAND SERVICES, INC. 221-4 Delta Court TALLAHASSEE, FLORIDA 32303 850-385-6255 (VOICE) 850-385-6355 (FAX)	PROJECT Oyster Bay Permit Modification Permit # 65-0245618-002DF Wakulla, Florida	TITLE Plan View-Canal Dredging	PAGE: 1
	DATE 4-16-08 Rev. 8-11-08	CHK: RBS	PROJ: 04-0325



3 of 7 8/30/16
65-0245618-004-EI



N.T.S.

AREA TO BE DREDGED
TOTAL QUANTITY =
4,240 CU. YDS. (INCLUDES
AREA ABOVE & BELOW MHW)



SELLERS CONSULTING, LLC

525 JOHN KNOX ROAD, SUITE D
TALLAHASSEE, FLORIDA 32303

PH: 850 386-7022
FAX: 850 386-7029

CIVIL ENGINEERING ENVIRONMENTAL PERMITTING LAND PLANNING
CERTIFICATE OF AUTHORIZATION NUMBER 20025

ROBERT B. SELLERS, P.E. FLA. REG. NO. 53217



Handwritten signature and date 8/16/16

Figure 5

FLORIDA ENVIRONMENTAL AND LAND SERVICES, INC. 221-4 Delta Court TALLAHASSEE, FLORIDA 32303 850-385-6255 (VOICE) 850-385-6355 (FAX)	PROJECT	Oyster Bay Permit Modification Permit # 65-0245618-002DF Wakulla, Florida	TITLE	Canal Dredging-Cross Section	PAGE:	2
	DATE	4-16-08 Rev. 8-11-08	CHK:	RBS	PROJ:	04-0325
					OF:	4



SCALE 1" = 50'



STATIONARY WALKWAY	=	24 SQ. FT.
FLOATING DOCK (INCLUDES RAMPS)	=	1,016 SQ. FT.
FINGER PIERS	=	516 SQ. FT.
TOTAL	=	1,556 SQ. FT.

SELLERS CONSULTING, LLC

525 JOHN KNOX ROAD, SUITE D
TALLAHASSEE, FLORIDA 32303

PH: 850 385-7022
FAX: 850 385-7029

CIVIL ENGINEERING ENVIRONMENTAL PERMITTING LAND PLANNING
CERTIFICATE OF AUTHORIZATION NUMBER 20055

ROBERT B. SELLERS, P.E. FLA. REG. NO. 53217

Handwritten signature and date 8/26/16


NOTE: PROPOSED SEAWALL, FLOATING DOCK,
FINGER PIERS AND STATIONARY WALKWAY
ARE TO BE DESIGNED BY OTHERS

Figure 6

FLORIDA ENVIRONMENTAL AND LAND SERVICES, INC. 221-4 Delta Court TALLAHASSEE, FLORIDA 32303 850-385-6255 (VOICE) 850-385-6355 (FAX)	PROJECT	Oyster Bay Permit Modification Permit # 65-0245618-002DF Wakulla, Florida	TITLE	Plan View-Docks	PAGE: 3
	DATE	4-16-08 Rev. 8-11-08	CHK:	RBS	BY:
					OF: 4



NOTE: DESIGN OF WALKWAY, DOCK AND
PIERS BY OTHERS.



N.T.S.

Robert B. Sellers, P.E.
8/22/16



SELLERS CONSULTING, LLC

525 JOHN KNOX ROAD, SUITE D
TALLAHASSEE, FLORIDA 32303
PH: 850 386-7022
FAX: 850 386-7029

CIVIL ENGINEERING ENVIRONMENTAL PERMITTING LAND PLANNING
CERTIFICATE OF AUTHORIZATION NUMBER 20555

ROBERT B. SELLERS, P.E. FLA. REG. NO. 53217

FLORIDA ENVIRONMENTAL AND LAND SERVICES, INC. 221-4 Delta Court TALLAHASSEE, FLORIDA 32303 850-385-6255 (VOICE) 850-385-6355 (FAX)	PROJECT Oyster Bay Permit Modification Permit # 65-0245618-002DF Wakulla, Florida	TITLE Dock-Cross Section	PAGE: 4
	DATE 4-16-08 Rev. 8-11-08	CHK: RBS	BY: 8-11-08



DAVID H. MELVIN, INC.
Consulting Engineers
4428 LAFAYETTE STREET
TALLAHASSEE, FLORIDA 32309
(850) 482-3315

2831 NORTON FOREST DRIVE, STE. 100
TALLAHASSEE, FLORIDA 32309
(850) 671-7221

3503 S. MONROE ST., STE. B
TALLAHASSEE, FLORIDA 32304
(850) 248-5111

PR. 4/20/2006

O. SEAN MARTIN, PE

[Signature]
1/11/2006

FLORIDA REG. #53939

Figure 90

FLORIDA ENVIRONMENTAL AND LAND SERVICES, INC. 285 PINEWOOD DRIVE TALLAHASSEE, FLORIDA 32303 850-385-6255 (VOICE) 850-385-6355 (FAX)	PROJECT Oyster Bay Canal Street Wakulla, Florida	Applicant: Charles Seely File: 20052601 NW-SWA Date: 27 February 2006 Page 4 of 8
---	---	---